AMC Quotation

An ISO 9001:2008 Certified Company

Quotation No - SQT 20-21-2468 **Date : 08.02.2021**

IKEA India Pvt Ltd
Indospace Industrial Park-Chakan II/III
Talawade Chakan Road,Mahalunge
Pune, Maharashtra, India

d Atte.: Mr. Ravindra Borage
mail ID: ravindra.borge@ingka.com
ontact: 7045598618

Subject: Offer for Comprehensive Annual Maintenance Contract (AMC) for Bailer Machine B-200/300 Building

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions. This has reference to your above
mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer :-

Sr. No.	Description	Financial Year	Rate/visit/Prodc ut	Total Product Qty(Nos)	No. of Visit/Year	Total Amount in Rs per
1	**Bailer machine Capacity; 15Ton** NIHVA make	2021	3000	1	4	12000
2	**Bailer machine Capacity; 20Ton** NIHVA make	2021	4500	1	4	18000
					Total Without Taxes	**30000**

SCOPE OF WORK:

Note :

1. **4 visits in a year (within 3 months 1 visit) 2 days per visit.for each visit we will submit you the below check point reports.**
2. **Work Time duration : 9 Hrs/day (9.00 AM to 6.00 PM)**
3. **Emergency breakdown charges will be Rs.7,500/- Extra per visit & Intimation for breakdown calls : Minimum 24 Hrs**
4. **Duration: From 01.02.2021 To 31.01.2022**

GST Pune :	27AAECN0437H1ZM
SAC Code	998729

Standard comprehensive AMC offer Servicing includes:

A. Mechanical: Check Points

Assembly checking-rotating parts and rollers.
Hydaraulic Power pack and compenents checking
Oiling/ greasing.
Other alignment & interlocking checking.
All Nuts-Bolts tightening.
Overhauling of Motion Parts (Mechanical linkages , Sprockets , bearings , etc. if any)

B. Electrical: Check Points

1 Main electric connections with motor & control panel connections.
2 Limit Switch Setting.
3 Control Box: Connectors, relay, overhead protection, switches.
4 And other Misc.
5 Electrical Connection checking , wire routing checking for wire damages , Load condition of all Drive motor , off load & On load

Consumable & Spare part list of the Bailer Machine;

Sr. No.	Description	Std Lead Time	Qty (Nos)	Unit	Unit Rate/Qty INR	Total Rate INR
1	M.S BUSH-OD80 X ID 40 X 50L and OD60 X ID 40 X 75L	3 Days	1	No	286	286
2	LM BUSH FLANGE MOUNTED-ID50	3 Days	1	No	214	214
3	FLEXIBLE HOSE 3/8 BSP (WORKING PRESS. 200 BAR)-(STRAIGHT X 90)	3 Days	1	Set	1,500	1,500
4	ADAPTOR-3 / 8 BSP	3 Days	1	Nos	171	171
5	BENJO-OD 16 PIPE	3 Days	1	No	29	29
6	ELBOW FITTING-OD 16 PIPE	3 Days	1	Nos	171	171
7	BONDED SEAL-3 / 4 BSP & 1 / 2 BSP	3 Days	1	Meter	29	29
8	HYDRAULIC CYLINDER-DOUBLE ACTING BORE 150 MM ROD 125	5 week	1	Set	71,250	71,250
9	TILTING CYLINDER SINGLE ACTING DIAMETER 60 MM ROD 50 MM STROKE 140 MM	4 week	1	Set	10,000	10,000
10	CONTROL PANEL-3 PHASE 4 POLE	4 week	1	Nos	25,000	25,000
11	LIMIT SWITCH medium lever;230V AC	3 Days	1	No	1,500	1,500
12	HYDRAULIC OIL-68 garde	3 Days	1	Litr	352	352
13	Hydraulic POWER PACK, 60 LITERS AC POWERPACK	5 week	1	Nos	71,429	71,429
14	3 TIER FLASHING LIGHT-230 VOLT 3 TIER	3 Days	1	Nos	1,850	1,850
15	FLEXIBLE CABLE WITH CONDUTE	3 Days	1	Meter	243	243
16	MOTOR 5 HP 3 PHASE 4 POLE 1440 RPM	4 week	1	Nos	25,000	25,000

Client Scope :

1	Above scope & charges includes servicing & attend the check points. If any major fault/repair, parts required replacement will be informed to you & attend at extra cost.
2	Customer should maintain sufficient stock of recommended spares to avoid delay. The list of required spares will be submitted on time by our Service Engineer.
3	Cleaned Space
4	Lifting Equipments required for inspection is in client scope
5	Electrical Power supply in Client Scope
6	Canteen Facility

Prerequisites for Service - Client Scope

1	The above terms do not apply in case of abuse, misuse, misapplication or any defects arriving due to negligence or accident. An extra cost will be applicable for Extra Man Power for extra. day (if required) + Spares & payable by you will be quoted separately.
2	The above terms do not apply to such products which shall have been installed, altered, or Repaired by any non-authorized person
3	Any spare part/ component (if) required, will be at extra costs are not inclusive in the maintenance contract
4	Required Forklift / Scaffolding and necessary help to our service Engineers from client during maintenance of each door in addition to any other charges or fees specified in this Agreement.
5	Additional Costs and Charges: The cost of materials and repair if any or extra services shall be charged extra to Customer.
7	If due to any reason our person need to wait beyond working duration, then Rs. 5,500/- per day working

Terms and Conditions :

1	Price :Ex. Works Pune
2	GST : Extra 18%
3	Validity :15 days from the date of quotation.
4	Payment : 100% within 30days after service/work completion

With Best Regards

Santosh Bangar
9168938333
For NIHVA Technologies Pvt Ltd