Sales Quotation

Quotation No - SQT/19-20/1901 **Date : 05.08.2019**

Emitec Emission control Technologies pvt.ltd
Hinjewadi
Pune

Kind Attn: Mr. Shrikant Biradar
Email: shrikant.biradar@continental-corporation.com
Mob.No. 9011041780

Project Name And Location :

Subject: Quotation for Dock Leveler, Scissor Lift , Retractable Dock Shelter

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Price/Each	Net Amount INR
A	**NIHVA Make Dock Leveller (6 TON)** **2 cylinder for Deck & 1 cylinder for LIP Operator by Standard Control Panel (Deck Up / Down / Lip Up / Down) Rubber Bumpers**				
1	Size : (W) 2200 mm X (L) 3000 mm **Supply & Installation**	2	No	230,000	460,000
B	**PIT MOUNTED SCISSOR LIFT TABLE Scissor Lift**				
	Capacity : 2 ton Platform : 3000L x 2000W Shut ht : 500 mm Max ht : 2000 mm Lift ht : 1500 mm Power pack : 3HP, 3PH Railing : both length side only Color : As per req.				
1	Supply + Installation	1	No	430,000	**430,000**
C	**PIT MOUNTED SCISSOR LIFT TABLE Scissor Lift**				
	Capacity : 3 ton Platform : 3000L x 2000W Shut ht : 600 mm Max ht : 2100 mm Lift ht : 1500 mm Power pack : 5HP, 3PH Railing : both length side only Color : As per req.				
1	Supply + Installation	1	No	465,000	**465,000**
D	**Dock Shelter - Retractable Type (Supply + Installation)**				
1	Size : (W) 3250 mm X (H) 3200 mm	4	No	150,000	600,000
E	**ASSA ABLOY - Sectional door (100% Imported products from Europe) OH 1042P** **Sectional door with Vertical Lift, Vision Windows, motor & control Panel, bottom safety edge and with all safety features** **Supply + Installation**				
1	Size (W) 3000 mm x (H) 3000 mm	4	No	314,250	1,257,000

GST Pune	27AAECN0437H1ZM

Technical Specifications of Dock Leveler

Sr. No.	Description	Specifications
1	Capacity	6 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	4 Ft
6	Travel above & below dock level	(+) 300 / (-) 150 mm
7	Platform Size (W x L)	2200 mm x 3000 mm
8	Lip size (W x L)	2200 x 400 mm
9	Shut Height	480 mm
10	Overall length	2200mm x 3000mm + Lip Length (400mm)
11	Maximum slope can be achieved	10%
12	Clear Pit dimensions (W x L x D)	(W) 2250mm x (L) 3000 mm x (D) 485 mm
13	Hydraulic power pack	Standard
14	Driver type	Direct by electric Motor
15	Motor Ratings	1 H.P Motor
16	Pump design flow	2.5 LPM
17	Pump pressure	120 bar Operating 200 bar Max.
18	Safety valve set pressure	120 Kg/cm²
19	Pump Type	Gear
20	Volume of oil receiver	7 Lit
21	No Of Deck cylinder	2 No
22	Lip Cylinder	1 No
23	Dock Bumper	Included

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places
3 Provide electrical cables near to the installation machinery
4 Hydra/crane at the time of Installation will be in NIHVA Scope.

Limit of Supply

1 Provide place to store the material to be installed
2 Be responsible for the safe custody of all material
3 Provide change & rest room for the workers

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Electrical connection for control panel

Client Scope

1 Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 NIHVA Will provided structure drawing only if required
4 Existing/Repair/ Modification/ Refurbishment charges will be extra

Terms and Conditions :

1	**Price**	:	Ex works Pune
2	**P & F Charges**	:	@ 3 % of total supply value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	5 -6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
5	**Payment**	:	80% Advance along with confirmed order, 20% before dispatch
6	**Taxes**	:	GST Extra @18%
7	**Validity**	:	Validity of Offer is 15 days from the date of quotation.
8	**Warranty**	:	24 months from the date of supply

Please feel free to Contact **Mr. Ravindra Kharat** on **7410169333** for any further Clarification /Information in this Concern.

With Best Regards

Varsha
8551091333
For NIHVA Technologies Pvt Ltd