NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

LANDSKY ALLIED INDUSTRIES PVT. LTD
(A Division of Landsky Group)
Plot No.35-69, 2nd Floor, G K Colony,
Sainikpuri Post Secunderabad - 500 094, Telangana, India

Date : 16.02.2021
Quote NO : SQT.20.21.3026
Kind Attn : Chandra Kanthi. G
Email Id : business@landskyallied.com
Contact No: 9100917096

Project Name & Location: Secunderabad

Subject : Quotation for NIHVA Make Dock Leveler , Dock Shelter & Sectional Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer -

Sr No	Description	Size		Qty	Ex Work Pune-Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Make Dock Leveler**	2000	3000	4	240,000	960,000	20,000	80,000
2	**Sectional Door - ASSA ABLOY Make 100% Impoted**	2400	3000	4	235,000	940,000	20,000	80,000
3	**NIHVA Make Rectratable Dock Shelter**	3600	4000	4	165,000	660,000	20,000	80,000
				Total		**2,560,000**		**240,000**
			P&F Charges	3%		**76,800**		
			Total Without Taxes			**2,636,800**		**240,000**
			GST Extra @ 18%	18%		474,624		43,200
			Total With Taxes			**3,111,424**		**283,200**
			Transportation Charges			**Extra at actual**		
			Unloading Charges @ Site			**In client scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Make Dock Leveler - 7 TON





Sr .No.	Specification	Specifications
1	Capacity	7 TON
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 / (-) 250 mm
7	Platform Size (W x L)	2000 mm x 3000 mm
8	Lip size (W x L)	2000 x 400 mm
9	Shut Height	480 mm
10	Overall length	3000mm + Lip Length (400mm)
11	Maximum slope can be achieved	10%
12	Clear Pit dimensions (W x L x D)	(W) 2050mm x (L)3000 mm x (D)485 mm
13	Hydraulic power pack	Standard
14	Driver type	Direct by electric Motor
15	Motor Ratings	1 H.P
16	Pump design flow	2.5 LPM
17	Pump pressure	120 bar Operating 200 bar Max.
18	Safety valve set pressure	120 Kg/cm²
19	Pump Type	Gear
20	Volume of oil receiver	7 Lit
21	No Of Deck cylinder	2 No
22	Lip Cylinder	1 No

NIHVA Make Rectratable Dock Shelter

Sr .No.	Specification	Specifications
1	Size	3600 (W) x 4000 (H) mm
2	Top Curtain	1000 mm
3	Side Curtain	600 mm
4	Curtain colour	Black
5	Parking Guides	White, Yellow
6	Wall Fixings	Concrete, Sandwich light Concrete, Load house cavity, insulated pane
7	Top & Side Curtains	Double Layer High Quality Polyester
8	Thickness	3.0 mm
9	Weight	Approx 3400 g/m2

Sectional Door -OH1042P Standred Lift

Sr. No	Description	Specifications
1	Day Light Width (DLW)	2400
2	Day Light Height (DLH)	3000
3	Total height floor to ceiling	3785
4	Enter Headroom	485
5	minimum required headroom	485
6	minimum required depth	3900
7	minimum required sideroom left	270
8	minimum required sideroom right	132
9	Door Weight	102
10	Calculated U-Value [W/m²K]	1.4
11	Number of panes	2
12	No of windows	2
13	Door panel finish	Pre-coat Steel panel as noted below
14	Shop Painted Colour Outside	Pre coated RAL colour to be decided from our standard range
15	Panel Colour Inside	Pre coat RAL 9002 Grey white
16	Horizontal Track Inclination	0
17	Min. load changes	20000
18	Windload Class	Class 3
19	Track Length L3 [mm]	3166
20	Number of stacked shafts	1
21	Position of Lock	LOCK LEFT
22	Section with Lock	2
23	Operator	CDM9 Single phase 230 volt motor unit
24	Recommended control cable length	3000
25	Type of track	6
26	Horizontal minimum depth (wall to end of track)	3900

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	In client scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In client scope
3	Electrical Supply on the site single phase/three phase points at different places.	In client scope
4	Any civil / masonry/structural work required	In client scope
5	All structure support required	In client scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In client scope
7	Conduits, Cables required	In client scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6-7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Shrikant Mirkute on 08551098333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd