NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SHARP DESIGNERS & ENGINEERS INDIA PVT. LTD.
Gat No. 301/2, Nanekarwadi,
Chakan, Tal : Khed, PUNE - 410 501

Date : 05.10.2020
Quote NO : SQT.20.21.2739
Kind Attn : Parag Keste
Email Id : parag_keste@sharpeng.com
Contact No: 9373990261

Project Name & Location: Shendra MIDC, Aurangabad

Subject : Quotation for Fire Rated Motorised Rolling Shutter.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**2 Hrs Fire Rated Motorised Rolling Shutter**	4000	4500	1	330,000	330,000	20,000	20,000
				Total Value		**330,000**		**20,000**
				P&F Charges	3%	9,900		
				Total Without Taxes		**339,900**		**20,000**
				GST Extra @ 18%	18%	61,182		3,600
				Total With Taxes		**401,082**		**23,600**
				Total (Supply + Installtion) with Taxes				**424,682**
2				Transportation Charges		**In Client Scope**		
3				Unloading Charges @ Site		**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications





2 Hrs. Fire Rated Rolling Shutters - 100% IMPORTED

- **Shutter Slats: Zinc coated steel solid slats**
- **Slat Thickness: 1.0mm thick**
- **Shutter Guide: Galvanize Steel, 3mm thick**
- **Operated by: Motor with one unit push button switch & manual override**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Price Pune

Delivery : 8 - 9 weeks from confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% advance along with purchase order & balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 18 months from the date of Installation.(Subject to date of installation within one month from date of supply)

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Amol Gaware on 7758820333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd