NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Wani Projects
Pune

Project Location : ESR Chakan .

Date : 03.02.2020
Quote NO : SQT.19.20.2371R
Kind Attn : Mr. Prashant Powar
Email Id : prashant.powar@wanigroup.com
Contact No:

Subject : Quotation for High Speed Door.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**HIGH SPEED PVC ROLL UP DOOR**	4500	4500	1	355,000	355,000	20,000	20,000
2	**Steel Sructure**			1	33,000	33,000		
3	**Transportation Charges**			1	7,000	7,000		
					Total	**395,000**		**20,000**
2	P&F Charges			3%		Nil		
	Total Without Taxes					395,000		20,000
	GST Extra @ 18%			18%		71,100		3,600
	Total With Taxes					**466,100**		**23,600**
3	Transportation Charges					**In Nihva Scope**		
4	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

HIGH SPEED PVC ROLL UP DOOR



- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels

Sr. No	Description	Specifications
1	**Use**	Internal Door
2	**Speed**	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	**Opening speed**	3 m/s
4	**Closing speed**	0.8 m/s
5	**Control Panel**	4 Push Button operated , Both Side.
6	**Security Features**	EN 13241-1 Standard
7	**Resistance to wind load**	EN12424 upto class 2
8	**Curtain**	Fabric Transparent PVC section
9	**Guide Material**	Aluminum
10	**Hood Cover**	GI
11	**Motor Cover**	GI
12	**Operator & Control**	German Make Motor
13	**Connecting Voltage**	220V , 1Ph , N
14	**Open-Stop-Close Button**	Standarad
15	**Protection Category**	IP 54 / IP 65
16	**Power Consumption**	0.75 kw Motor
17	**Emergency Off Button**	Standard
18	**Closing Zone Monitoring**	Optical Safety edge
19	**External Route Monitoring**	Photocell
20	**Emergency Opening**	Crank Handle

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd