NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0079 **Date : 12-12-2017**

Procter and Gamble home product pvt ltd
Survey no.- 280,Penjerla Village,kothure
mandal, rangareddy
Telangana

Kind Attn : Mr. Manoj khachane
Email : khachane.ml@pg.com
Contact No : 8602351416

Subject : Quotation for Telescopic Conveyor

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
Telescopic Conveyor Make - NIHVA (HSN CODE : 84289090)					
Technical Specifications	• Length of Conveyor : 17000 mm	**1**	**No**	**17,45,000**	**17,45,000**
	• Extended Length of Conveyor : 12000 mm				
	• Fixed Length of Conveyor : 5000 mm				
	• Width of Conveyor : 1000 mm				
	• Material to be handle : Polywoven Bags				
	• Weight of Material : 6-30 kg/each				
	• Material of Construction : MS Painted				
	• Loading Height From Shop Level : 1500 mm				
	• Speed Of Conveyor : 30 mtr/min Max.				
	• Temperature : Ambient				
	• Drive Motor : 7.5 HP Coupled Geared Motor				
	• Stepper Motor, Sensor and Control Panel				
Installation ,Comissioning & Training Charges		**1**	**No**	**20,000**	**20,000**

GST PUNE:	**27AAECN0437H1ZM**
GST GUJRAT:	**24AAECN0437H1ZS**

Amount in Words	**Total Amount**	**17,65,000**
	Rupees Seventeen Lacs Sixty Five Thousand Only	

Image Attached For your Reference



Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client
2 All structure support is in client scope
3 NIHVA Will provided structure drawing only if required
4 Existing Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	3% Extra
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	8-9 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing
5	**Payment**	:	80% advance along with confirm Purchase Order & balance before dispatch
6	**Insurance**	:	Extra if applicable
7	**Tax**	:	GST: Extra as applicable at the time of delivery.
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre
7709586333
For Nihva Technologies Pvt Ltd