NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Lupin Limited
Ghotawade,pirangut

Date : **23.12.2019**
Quote NO : **SQT.19.20.2274R3**
Kind Attn : **Mr. Dheeraj Sawant**
Email Id : dheerajsawant@lupin.com
Contact No: **9833273706**

Subject : Revise Quotation for High Speed Door, Rolling Shutter and Dock Leveller.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2,3
C.	General Conditions	4
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Double wall Rolling Shutter**	3000	3500	2	187,000	374,000	15,000	30,000
2A	**Option 1 : Self Repairable Function Albany Make Rapid Roll Up Door - HS9020G**	2500	3500	3	479,000	1,437,000	15,000	45,000
2B	**Option 2 : Non Self repairable Function Albany Make Rapid Roll Up Door - RR300 S**	2500	3500	3	521,000	1,563,000	15,000	45,000
3	**Nihva make Dock Leveller(9 Ton)**	2000	2500	2	220,000	440,000	15,000	30,000
4	**Interlocking (RS + DL)**			2	20,000	40,000		-
				Total				
5	P&F Charges			Nil		-		
	Total Without Taxes					-		-
	GST Extra @ 18%			18%		-		-
	Total With Taxes					-		-
6	Transportation Charges					**Included**		
7	Unloading Charges @ Site					**At Nihva Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Option - 1 : Self repairable function

HS9020G




HS9020G



SIDE GUIDES



Safety Facilities



Sr. No	Description	Specifications
1	**Structure**	Galvanized steel
2	**Colours**	8 standard colors - white, yellow, green, orange, red, gray, black, blue
3	**Safety**	• Photocells in side columns • Flexible soft bottom edge including wireless edge activator • Break-away and self-repair function
4	**Operation**	Operator + control unit
5	**Operating speed**	Opening: up to 1,2 m/s (optional 2,0 m/s) ; Closing: 0,5 m/s
6	**Wind load resistance**	Class 1 (300 Pa (N/m²)) maximum wind load while closing 50 N/m²
7	**Air permeability**	Class 1 (24 m³/m²/h at 50 Pa)
8	**Water penetration**	Class 2 (50 Pa (N/m²))
9	**Thermal transmittance**	6,02 W/(m²K)
10	**Lifetime expectations**	1.000.000 cycles
11	**Temperature working range**	5 °C to +40 °C
12	**Vision window**	Horizontal one row of height 400 mm at eye level
13	**Loop Detector for both Side**	6 Set (Only for Metal Detection, for men movement use control pannel button)
14	**Interlock with BMS**	Included (Yes , Only for High Speed Door, for 3 Doors 3 Sets)

B) Technical Specification

Option - 1 : Non - Self repairable function


RR300 S



RR300 S



Motor and Control Panel



Color options

Sr. No	Description	Specifications
1	**Structure**	Galvanized steel
2	**Colours**	8 standard colors - white, yellow, green, orange, red, gray, black, blue
3	**Safety**	• Electrical safety contact edge • door line photocell
4	**Operation**	Operator + control unit
5	**Operating speed**	Opening: up to 2.3 m/s ; Closing: 1.0 m/s
6	**Wind load resistance**	class 1 (EN 12424).
7	**Bottom Profile**	Anodized Aluminum
8	**Protection**	IP55
9	**Control System**	Frequency converter control system MCCVectorControl, based on vector control including boost function at start-up. Graphic display and foil keypad for easy guided operation. Easy access to all important information regarding operation and service
10	**Supply voltage:**	3L(N)PE/380/400/415/440/480V;50/60Hz
11	**Loop Detector for both Side**	6 Set (Only for Metal Detection, for men movement use control pannel button)
12	**Interlock with BMS**	Included (Yes , Only for High Speed Door, for 3 Doors 3 Sets)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) **Double Wall Rolling Shutter**

Description	Specifications
GI Slat :	19 mm Thick
Profile :	Curved Type Profile with heavy duty Shaft
Guide :	2.5 mm Thick MS Guid
Hood Cover & Motor Cover :	0.9 mm Thick GI material
Motor :	Indirect Drive
Acessaries:	Photocell

D) **Dock Leveller**

Description	Specifications
Capacity	9 Ton
Dock operation mode	AC power pack hydraulically operated
Lip operation mode	Hydraulic
Operation control	Through panel
Loading platform height from road	1250mm
Travel above & below dock level	(+) 300 / (-) 250 mm
Platform Size (W x L)	2000 mm x 2500 mm
Lip size (W x L)	2000 x 400 mm
Shut Height	480 mm
Overall length	2000mm x 2500mm + Lip Length (400mm)
Maximum slope can be achieved	10%
Clear Pit dimensions (W x L x D)	(W) 2050mm x (L) 2550 mm x (D)485 mm
Hydraulic power pack	Standard
Driver type	Direct by electric Motor
Motor Ratings	1 H.P
Pump design flow	2.5 LPM
Pump pressure	120 bar Operating 200 bar Max.
Safety valve set pressure	120 Kg/cm²
Pump Type	Gear
Volume of oil receiver	7 Lit
No Of Deck cylinder	2 No
Lip Cylinder	1 No
Yellow and Black Strips for Side Guide	Included
Dock Bumper	Pair of Dock Bumper
Dock Bumper steel Gard	Steel Support Plates
Operation	not stopping automatic while any truck movement

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	NIHVA
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : At Site

Delivery : 12-13 Weeks for High Speed Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333.**

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd