NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Harnish Pharma
Mehsana, GJ

Date : 16.02.2023
Quote NO : MHE_22.23.0033R
Kind Attn : Mr. Surdip A. Chaudhary
Email Id : surdip@harnishpharma.com
Contact No: 99789 20328

Project Name & Location: Harnish Pharma, Mehsana

Subject : Commercial Offer for Pit Monuted Hydraulic Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in INR		Installation Charges in INR	
		Working Platform (in mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Pit Monuted Hydraulic Scissor Lift** ● Capacity : 1500 Kg ● Lift Height : 1000 mm	2500 L mm X 2000 W mm	6	3,20,000	19,20,000	Included	
2	**Pit Monuted Hydraulic Scissor Lift** ● Capacity : 1500 Kg ● Lift Height : 1000 mm	2000 L mm X 2000 W mm	1	3,30,000	3,30,000	Included	
			Total				**22,50,000**
		Total Without Taxes					**22,50,000**
3	GST Extra @ 18%		18%				**Extra At Actual**
4	P&F Charges on Total Supply Value		3%				**Extra At Actual**
5	Transportation Charges						**In Client Scope**
6	Unloading Charges @ Site						**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Pit Monuted Hydraulic Scissor Lift

Sr. No	Description	Specifications
1	**Capacity**	1500 Kg
2	**Platform size**	(L) 2500 mm X (W) 2000 mm & (L) 2000 mm X (W) 2000 mm
3	**Shut Height**	500 mm
4	**Lift Height from ground level**	1000 mm
5	**Total Height**	1500 mm
6	**Lip Size**	Two Side Lip - Size: 450 mm (W) X 2000 mm (L)
7	**Type of platform**	Chequered plate
8	**2-Side Fixed Railings, Height 900 mm**	
9	**2- Push Button (position on railing & on control panel)**	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA which is at an additional cost.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material.
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required.
5	All structure support required.
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-9 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 60% Advance along with Confirmed Purchase Order.
35% Along with Approval of Drawing and before start a Production.
5% Against completion of Installation, Testing and Commissioning.

Validity : Validity of Offer is 7 days from the date of quotation

Warranty : 12 months from the date of supply.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd