NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SCON Projects Pvt. Ltd
Samarth House,
S.NO.116, Hissa No.3/1, 3/3,3/10,
Pune - Bangalore Highway,
Near Shell petrol Pump,
Warje, Pune – 411058.

Date : **28.01.2020**
Quote NO : **SQT.19.20.2366**
Kind Attn : **Mr. Jitesh S. Darvatkar**
Email Id : jiteshd@sconprojects.com
Contact No: **8928770959**

Subject : Quotation for High Speed Door HS9020G

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
	Option - 1							
	Albany Make Rapid Roll Up Door HS9020G	2000	3000	1	462,000	462,000	20,000	20,000
	Option - 2							
	NIHVA Make High Speed Door	2000	3000	1	298,000	298,000	20,000	20,000
				Total				
	P&F Charges			3%		-		
	Total Without Taxes					-		-
	GST Extra @ 18%			18%		-		-
	Total With Taxes					-		-
	Transportation Charges					**In Client Scope**		
	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company


GST Pune : 27AAECN0437H1ZM

B) Technical Specification **Albany Make Rapid Roll Up Door**









HS9020G **SIDE GUIDES** **Safety Facilities**

Sr. No	Description	Specifications
1	Structure	Galvanized steel
2	Colours	8 standard colors - white, yellow, green, orange, red, gray, black, blue
3	Safety	• Photocells in side columns • Flexible soft bottom edge including wireless edge activator • Break-away and self-repair function
4	Operation	Operator + control unit
5	Operating speed	Opening: up to 1,2 m/s (optional 2,0 m/s) ; Closing: 0,5 m/s
6	Wind load resistance	Class 1 (300 Pa (N/m²)) maximum wind load while closing 50 N/m²
7	Air permeability	Class 1 (24 m³/m²/h at 50 Pa)
8	Water penetration	Class 2 (50 Pa (N/m²))
9	Thermal transmittance	6,02 W/(m²K)
10	Lifetime expectations	1.000.000 cycles
11	Temperature working range	5 °C to +40 °C
12	Vision window	Horizontal one row of height 400 mm at eye level

Technical Specification **NIHVA Make High Speed Door**

- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels



Sr. No	Description	Specifications
1	Use	Internal Door
2	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	Opening speed	3 m/s
4	Closing speed	0.8 m/s
5	Control Panel	4 Push Button operated
6	Security Features	EN 13241-1 Standard
7	Resistance to wind load	EN12424 upto class 2
8	Curtain	Fabric Transparent PVC section
9	Guide Material	Aluminum
10	Hood Cover	GI
11	Motor Cover	GI
12	Operator & Control	German Make Motor
13	Connecting Voltage	220V , 1Ph , N
14	Open-Stop-Close Button	Standarad
15	Protection Category	IP 54 / IP 65
16	Power Consumption	0.75 kw Motor
17	Emergency Off Button	Standard
18	Closing Zone Monitoring	Optical Safety edge
19	External Route Monitoring	Photocell
20	Emergency Opening	Crank Handle

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 12-13 Weeks for High Speed Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Ulka Auti.
7219206333
For NIHVA Technologies Pvt Ltd