NIHVA

NIHVA TECHNOLOGIES PVT. LTD.







HAL Project @Bangalore, India



Quotation

ASSA ABLOY

ASSA ABLOY Entrance Systems

The global leader in
door opening solutions

Quotation reference: **SQT/19-20/1454**

Date: 12th April 2019

CPWD
Bangalore India

Kind Attn: Mr. Rajesh Jain
Contact No: 8826618109
Email: cpmhalsz@gmail.com

Project: HAL Hangar Project at Bangalore, India

Dear Sir,
Thank you for giving us an opportunity to participate with our offer on the above project. We enclose herewith our proposal which includes:

A. PRICING -

Supply Price includes Custom Duty, custom clearance, Local Transport:

Sr. No	Description	Price/Each in Rs	Qty No	Total Price in INR
1	Supply of above Hanger Door **(W)60 mtr x (H)7 mtr**	3,53,35,000	1	**3,53,35,000**
2	Supply of above Hanger Door **(W)20 mtr x (H)5 mtr**	92,30,000	1	**92,30,000**

General Pre-Requisites Required at Site

Prerequisites:
1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery.

Limit of Supply
1.Provide place to store the material to be installed.
2. Be responsible for the safe custody of all material including Installation Tools and Equipments.
3. Provide change & rest room for the workers.

Terms &Conditions:

Payment : 80% advance along with Confirmed Purchase Order and Balance before Dispatch.

P & F Charges : NIL

Transport : Included in above Prices

GST : @18% extra on Supply & installation

Validity : 45 days

Delivery : 22-23 weeks from the date of receipt of confirmed order, advance payment, drawing approval

Insurance : Extra as applicable

Warranty : 12 months from date of Supply

General conditions of Aircraft Hangar Door (VL 3190)

1. Continuous uninterrupted access to any single door section or as agreed separately.

2. A clear floor area of 4 metres each side of the door leaf must be available during the curtain fitting process. The floor should be finished or if this is not possible, adequate temporary protection be made available to prevent damage to the curtain material.

3. 400 volt / 50Hz 3 phase isolator to be fitted to within 1 metre of the door main control panel. If not available at the start of installation, a temporary supply is acceptable. Any return visits to commission the doors due to permanent power not being available will be charged as appropriate.

4. A suitable structure should be available together with mullion floor pits (multiple section doors only) designed in accordance with final approval drawings issued by ASSAABLOY. Tolerances/deflections of the support structure to be in accordance with the drawings.

5. Provision of 230 Volt power supply (by others) for hand tools.

6. A dry and secure area, not in direct sunlight, is to be provided for storage of the door components.

7. Access to site between 7 am to 6 pm six days per week. If this is not possible the installation programme may require amending.

8. Any storage costs for materials due to delays outside of Mega door's control will be charged to the main contractor.

9. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practices. We reserve the right to extend the period accordingly.

10. Any passes required for the project, are the responsibility of the Customer and Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.

Inclusions

1. Our proposal includes **sea freight from Sweden to Site and installation of the door leaf, guide rails, weather seals, motors, control panel.** (Please refer Exclusion)

2. A pre-installation inspection will be carried out, by our Project Manager, before our installers travel to site, so as to verify that the structural steelwork and electrical installation are as per our requirements. Our Project Manager will also check that the installation equipment and facilities are ready for installers.

3. Please note that the control panels, motors and electrical wiring are in full compliance with Swedish regulations and specifications, any variations due to specific requirements for India must be notified to us at the time of ordering and may be subject to an increase in the price. Any variations notified to us, after material procurement, will be charged accordingly and may lead to production delays.

4. A load test on all points in the door opening, as specified by our design department. A load test report is to be submitted to our Project Manager after the test is completed (to be done by main contractor).
5. Conduits and Cable trays from the control panel locations to the door distribution boxes, mullion hoist units and door hoist units be provided. (to be done by electrical contractor).These are to be installed prior to the commencement of door installation.

Exclusions

The following items are not within our scope of works and are to be provided by others at no cost to NIHVA - ASSAABLOY.

1. A compliance statement, with supporting documentation, which states that the building deflections are in accordance with the criteria, as agreed between our design department and the steelwork contractor (to be done by main contractor).

2. The structural support steel for the door head, jambs, motor plates, mullion wind bracing, and mullion motors shall be furnished by Main Contractors. Structural steel supports shall be installed in accordance with tolerances shown on Mega door shop drawings. The installation will not commence until these items are fully installed and tested (by steelwork contractor). The installation must be approved by the Megadoor Project Manager.

3. Any civil work required for Structural Support (to be done by civil contractor)

4. Mullion pits, as per our design (to be done by civil contractor).

5. Any passes required for the project, are the responsibility of the Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.

6. A 400/230 power supply (permanent or temporary) must be provided (FOC) by the main Contractor during the installation of the door for power tools and testing of the door sections during erection.

7. A safe storage / pre-assembly area for the door materials (by main contractor).

8. Any additional tests or certification, which are not within our scope of works but may be required by the Consultant or Client, these will be carried out or provided, subject to the actual requirements but will be at additional cost (by main contractor).

A. TERMS & CONDITIONS:

I. Final design

Please note that the final design of the doors is subject to the final design of the building structure; the final door configuration will be agreed after the contract is awarded.

II. Preliminary schedule

The schedule below is preliminary. The schedule times will change subject to the final choice of door design. Critical milestones are receipt of the LPO, receipt of the advance payment, final approval of shop drawings, and successful load test of the building and overall site readiness for the door installation.

Placement of Order and Order clarification	Week 1
Fast track approval letter (Optional)	Week 1
Supply of Shop Drawings	Week 2
Detailed Design	Week 4
Completion of Component Production	Week 15
Shipment ex works	Week 15
Sea freight	Week 16
Delivery of Goods at CIF Mumbai	Week 22

Installation time is subject to site readiness, clear working area and delays by others. Detailed program will be agreed with our project coordinator.

III. Delivery conditions

Delivery of material will be coordinated with the client written construction schedule. The contractor is responsible for notification to Megadoor of any expected or actual delays in the agreed delivery date at least fourteen (14) days prior to the scheduled delivery. Without timely notification of changes in delivery dates, the contractor or contractor's representative will assume the responsibility of unloading and storing the provided materials in a manner to prevent damage of the materials.

IV. Drawings

We will issue a full set of shop drawings for approval within 2 weeks of receiving the confirmed order and finalized design details

V. Compensation clause

Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA - ASSAABLOY a compensation of 25% of order value.

ASSA ABLOY Entrance Systems

One partner for all your automatic entrances

ASSA ABLOY Entrance Systems comprise world-leading products, maintenance programs and modernization services, ensuring total solutions for efficient flow of people, goods and vehicles. With comprehensive entrance solutions for the front, back and interior of your building, we put every automatic door equipment or service you need under one roof.

The perfect match for your building
ASSA ABLOY Entrance Systems' extensive product range, expert application knowledge and maintenance programs provide optimal entrance solutions for all needs and any demands in manufacturing, distribution & logistics, retail, healthcare, transportation, hospitality, private services, public services, mining and air & sea, and more.

Sustainable Solutions
We design, manufacture and service automatic entrance solutions that help you reach your sustainability goals for energy savings and minimal environmental impact.

Leading product brands backed by dedicated specialists
With our three specialized business areas; Pedestrian Door Solutions, Industrial Door & Docking Solutions and High-Performance Door Solutions, we offer market-leading product brands and a global service organization. With more than a century of aggregated engineering experience and application expertise ASSA ABLOY Entrance Systems is your ideal business partner to provide, maintain and modernize all of your automatic entrances.



Pedestrian Door Solutions

- swing doors
- sliding doors
- revolving doors



Industrial Door and Docking Solutions

- industrial doors
- complete docking systems
- hangar doors



High-Performance Door Solutions

- high speed roll doors
- doors for special applications such as clean rooms, machine protection and food processing