NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

HI-TECH PROJECTS PRIVATE LIMITED
B-401, Solitaire Corporate Park
Nr. Divya Bhaskar House
S. G. Highway, Ahmedabad 380051

Date : 31.03.2021
Quote NO : SQT.20.21.3122 R
Kind Attn : Charmil Shah
Email Id : tender@hitechprojects.co.in
Contact No: 9724058148

Project Name & Location: Bhilosha Industries

Subject : Revised quotation for Motorised Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Conditions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorised Rolling Shutter - MS or GI**	3000	3000	1	85,000	85,000	20,000	20,000
2	**Motorised Rolling Shutter - MS or GI**	3000	4000	1	95,000	95,000	20,000	20,000
3	**Gear Operated Rolling Shutter - MS or GI**	3000	3000	1	60,000	60,000	20,000	20,000
4	**Gear Operated Rolling Shutter - MS or GI**	3000	4000	1	70,000	70,000	20,000	20,000
5	**Manual Push pull Rolling Shutter - MS or GI**	3000	3000	1	50,000	50,000	20,000	20,000
6	**Manual Push pull Rolling Shutter - MS or GI**	3000	4000	1	60,000	60,000	20,000	20,000
7	**Extra Grill - 1000 mm Height**	3000 mm Width		1	4,500	4,500		-
			Total			**424,500**		**120,000**
8	P&F Charges			3%		**12,735**		
	Total Without Taxes					**437,235**		**120,000**
	GST Extra @ 18%			18%		78,702		21,600
	Total With Taxes					**515,937**		**141,600**
9	Transportation Charges					Extra at actual		
10	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter





Sr .No.	Specification	MS / GI Motorized Rolling Shutter
1	Description:	Motorised Rolling Shutter with MS /GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	On Concrete /Steel
4	Curtain Panel	The panel made of 1.0mm thick GI / MS
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile -as per the opening width dimension
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 0.9 mm
12	Surface finish	Powder Coated for GI & 2 Coat PU enamel paint
13	Drive Unit & Mounting Type - Motorised	Electric Motor - In Direct Drive - Sprocket chain arrangement – IP54 Protection
14	Drive Unit & Mounting Type - Gear Operated	Gear Assembly - Opening one side only
15	Drive Unit & Mounting Type - Push Pull	Manual Push Pull

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 3-4 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% along with confirmed purchase order & Balance before dispatch

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd