NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

LG Electronics India Pvt Ltd
Plot No . A-5| MIDC, Ranjangaon,
Tal: Shirur ,Dist: Pune - 412 220
Maharashtra -India

Date : 10.10.2019
Quote NO : SQT.19.20.2123R1
Kind Attn : Mr. MANTHESH PATIL
Email Id : mahantesh.patil@lge.com
Contact No: **9168600204**

Project Name & Location: LG Electronics India Pvt Ltd , Pune

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	PIT MOUNTED ELECTRO HYDRAULIC SCISSOR LIFT	1200	2000	1	250,000	250,000	20,000	20,000
				Total		**250,000**		**20,000**
2			P&F Charges	3%		**7,500**		
			Total Without Taxes			**257,500**		**20,000**
			GST Extra @ 18%	18%		46,350		3,600
			Total With Taxes			**303,850**		**23,600**
3			Transportation Charges			**In Client Scope**		
4			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

PIT MOUNTED ELECTRO HYDRAULIC SCISSOR LIFT

Description	Specification
Capacity	250 kgs
Platform Size	2000L x 1200W
Shut ht	300 mm
Max ht	1300 mm
Lift ht	1000 mm
Power pack	2HP, 3Phase
Safty	Safty Bellow from all Side.
REQ. PIT SIZE	2050L X 1350W X 310H
Railing	Only two side 300 mm height on platform.
Colour	As required

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333.**

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd