**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**CLOOS INDIA WELDING TECHNOLOGY PRIVATE LIMITED**
Hauptverwaltung: Carl-Cloos-Straße 1
Zentrallager: Carl-Cloos-Straße

**Date : 04.03.2020**
**Quote NO : SQT/19-20/2474**
**Kind Attn : Mr.Jayram Epilli**
**Email Id : Jayram.Epilli@cloos.de**
**Contact No: 7020780534**

**Subject : Quotation for Motorised Single Leaf Sliding Gate .**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 2 |
| D. | Terms & Condtions | 2 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **MOTORISED SINGLE LEAF SLIDING GATE** | 17000 | 1900 | 1 | 379,000 | 379,000 | 20,000 | 20,000 |
| | | | | **Total** | | **379,000** | | **20,000** |
| 2 | | | P&F Charges | 3% | | 11,370 | | |
| | | | **Total Without Taxes** | | | 390,370 | | 20,000 |
| | | | GST Extra @ 18% | 18% | | 70,266.60 | | 3,600 |
| | | | **Total With Taxes** | | | **460,637** | | **23,600** |
| 3 | | | Transportation Charges | | | In Client Scope | | |
| 4 | | | Unloading Charges @ Site | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

| NIHVA MAKE – MOTORISED SINGLE LEAF SLIDING GATE | |
|---|---|
| **Door type** | **Motorized Sliding Gate** |
| **Clear Opening gate dimension** | (W) 17000 x (H) 1900...in mm |
| **Opening Direction** | **Horizontal - from left to right or reverse** |
| **Mounting Location area** | Inside area |
| **Design Pattern** | Standard Tubular Design Pattern |
| **Outer Frame Tube Sizes** | 50X50X3 MM MS SQ. TUBE |
| **GI SHEET** | 11000X1900X0.9 THK |
| **FOR POST** | 50X50X3 MM MS SQ. TUBE |
| **Bottom Rail on ground** | dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams |
| **Bottom Rollers** | Heavy Duty Bottom Wheel With both side Bearings (chorme plated) |
| **Guide Rollers supporter during Gate movement** | **Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate** |
| **Painting** | 2 Coats of EPOXY polyamide based enamel finish of approved colour |
| **El motor make** | BFT – Italy (100% imported) |
| **Emergency Operation** | Manual after turn the switch |
| **Operating Switch** | Push Button from inside |
| **Safety** | Photocells, Flashing Light , Buzzer |
| **Vision Window** | 500 mm X 500 mm |
| **Metal Rack** | zinc plated metal rack |

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr.Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd