NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

HI-TECH PROJECTS PRIVATE LIMITED
B-401, Solitaire Corporate Park
Nr. Divya Bhaskar House
S. G. Highway, Ahmedabad 380051

Date : 08.11.2020
Quote NO : SQT.20.21.2815
Kind Attn : **Vinit Shah**
Email Id : tender@hitechprojects.co.in
Contact No: 8320292277

Project Name & Location: Gandhinagar

Subject : Quotation for GI Motorised Rolling Shutter and Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Conditions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	MOTORIZED SINGLE LEAF SLIDING GATE	9000	1500	1	428,563	428,563	20,000	20,000
2	G I Motorised Rolling Shutter - Direct Drive	5000	3750	1	273,086	273,086	20,000	20,000
3	G I Motorised Rolling Shutter - Direct Drive	4050	3750	1	217,662	217,662	20,000	20,000
4	G I Motorised Rolling Shutter - Direct Drive	3000	3000	1	186,531	186,531	20,000	20,000
			Total			**1,105,842**		**80,000**
5	P&F Charges			3%		**33,175**		
	Total Without Taxes					**1,139,017**		**80,000**
	GST Extra @ 18%			18%		205,023		14,400
	Total With Taxes					**1,344,040**		**94,400**
6	Transportation Charges					Extra at actual		
7	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter





Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	On Concrete /Steel
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm
12	**Surface finish**	Powder Coating
13	**Drive Unit & Mounting Type**	Electric Motor - Direct Drive - Sprocket chain arrangement – IP54 Protection

	Specification	Sliding Gate
1	**Door type**	**Telescopic Sliding Gate**
2	**Opening Direction**	**Horizontal - from left to right or reverse**
3	**Mounting Location area**	**Inside Area**
4	**Design Pattern**	**Standard Tubular Design Pattern**
5	**Outer Frame Tube Sizes**	100x100x4mm MS SQ. TUBE
6	**INNEAR TUBE**	38x38x.62 mm MS SQ. TUBE
7	**Gap Between Tubes**	125mm
8	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
9	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
10	**Guide Rollers supporter during Gate movement**	**Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate**
11	**Painting**	2 Coats of EPOXY polyamide based enamel finish of approved colour
12	**EI motor make**	BFT – Italy (100% imported)
13	**Emergency Operation**	Manual after turn the switch
14	**Operating Switch**	Push Button from inside
15	**Safety**	Photocells, Flashing Light
16	**Metal Rack**	zinc plated metal rack

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% along with confirmed purchase order & Balance before dispatch

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd