**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Amcor Flexible India Pvt. Ltd**
GAT NO. 222/152 A, TALEGAON-CHAKANA ROAD
VILLAGE-MAHALUNGE, TAL-KHED
DIST. PUNE- 410501

**Date : 16.03.2020**
Quote NO : SQT.19.20.2500
**Kind Attn :** Mr. Umeshkumar Ragde
Email Id : umeshkumar.ragde@amcor.com
Contact No: 7506222915

**Subject : Quotation for High Speed Door.**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Length (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **HIGH SPEED PVC ROLL UP DOOR** | 2880 | 3500 | 1 | 305,000 | 305,000 | 20,000 | 20,000 |
| 2 | **HIGH SPEED PVC ROLL UP DOOR** | 2000 | 2430 | 1 | 283,000 | 283,000 | 20,000 | 20,000 |
| 3 | **Interlocking of Doors** | | | 1 | | 18,000 | | |
| | | | | | **Total** | **606,000** | | **40,000** |
| 4 | P&F Charges | | | 3% | | 18,180 | | |
| | **Total Without Taxes** | | | | | 624,180 | | 40,000 |
| | GST Extra @ 18% | | | 18% | | 112,352 | | 7,200 |
| | **Total With Taxes** | | | | | **736,532** | | **47,200** |
| 5 | Transportation Charges | | | | | **In Client Scope** | | |
| 6 | Unloading Charges @ Site | | | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**HIGH SPEED PVC ROLL UP DOOR**



- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels
- Advance & robust Control Device

| Sr. No | Description | Specifications |
|---|---|---|
| 1 | Use | Internal Door |
| 2 | Speed | Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking |
| 3 | Opening speed | 3 m/s |
| 4 | Closing speed | 0.8 m/s |
| 6 | Security Features | EN 13241-1 Standard |
| 7 | Resistance to wind load | EN12424 upto class 2 |
| 8 | Curtain | Fabric Transparent PVC section |
| 9 | Guide Material | Aluminum Standard (Stainless Steel Optional) |
| 10 | Hood Cover | GI |
| 11 | Motor Cover | GI |
| 12 | Operator & Control | German Make Motor , VFD |
| 13 | Connecting Voltage | 220V , 1Ph , N |
| 14 | Open-Stop-Close Button | Standarad |
| 15 | Protection Category | IP 54 / IP 65 |
| 16 | Power Consumption | 0.75 kw Motor |
| 17 | Emergency Off Button | Standard |
| 18 | Closing Zone Monitoring | Optical Safety edge |
| 19 | External Route Monitoring | Photocell |
| 20 | Emergency Opening | Crank Handle |
| 21 | Pulll chord Cable and Vision Window | Included |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Transportation** : Extra as applicable

**Delivery** : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333.**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd