Purchase Order No: ATPL/S/16/354
Ref No: UBS/GST/17/253

Date: 22.01.2019

M/S. NIHVA TECHNOLOGIES PVT LTD
187, G-BLOCK, THERMAX CHOWK, MIDC
CHINCHWAD, PUNE – 411019
Contact: +91 8551091333
Email: support@nihva.com
GST No.: 27AAECN0437H1ZM
PAN No.: AAECN0437H

Kind Attention: Kind Attention: Mr. Vijay Tarak
Managing Director
Contact No.: +91 8551093333
Email: sales@nihva.com

Ref: Your Quotation No - SQT/18-19/0885R3 dated 16.01.2019

Dear Sir,

Purchase Order for:
SUPPLY AND INSTALLATION OF HIGH SPEED DOOR AT OUR FACTORY IN SANJAN, UMBERGAON

SR. NO.	DESCRIPTION	QTY	UNIT	RATE IN INR	TOTAL AMOUNT IN INR
A	**High speed door ASSAABLOY (Albany) HS9020G: made in Germany**				
1	Size (w) 2.42 m x (h) 3.0 m (Supply & Installation)	11	Nos.	3,55,000.00	39,05,000.00
				TOTAL	**39,05,000.00**
				GST @ 18%	**7,02,900.00**
				GRAND TOTAL	**46,07,900.00**

Total Rs. 46,07,900/- (Rupees Forty Six Lakh Seven Thousand Nine Hundred Only).

CIN No. U15490MH1990PTC054836
ADMIN. OFFICE : 61, DR. S. S. RAO ROAD, NEAR M. G. HOSPITAL, PAREL, MUMBAI - 400 012
TEL : 91-22-4040 0900 ● FAX : 91-22-2411 9489 ● Website : www.societytea.com ● Email : info@societytea.com

Purchase Order No: ATPL/S/16/354
Ref No: UBS/GST/17/253

This price is inclusive of:

1. Delivery at site (FOR site, including Transit insurance etc. complete).
2. Packing forwarding charges are included in above prices.
3. Installation and commissioning.
4. Your engineers will set each machine and impart training to our concerned personnel.
5. Transportation to & fro and lodging & boarding are all to your account.

All safety measures of your engineer like insurance / PF / ESIC etc. are to your account as per statutory requirements

TECHNICAL SPECIFICATIONS:

Operating speed	opening: up to 1,2 m/s closing: 0,5 m/s The fast opening and closing speed improves your traffic flow, provides employee comfort, and saves energy.
Wind load resistance	class 1 (300 N/m2), maximum wind load while closing 50 N/m2
Safety features	Technical details: a. The soft bottom edge has no rigid parts, it moulds around any obstruction to prevent injury or damage b. When an object hits the door, the fabric curtain absorbs the impact and releases itself from its side guides without causing damage or being damaged itself c. Push button both side d. Photocell - One side internal e. RAL color 7035 (Light Grey) f. Magnetic loop detector (outside only) size / location etc. to be decided at site. Proper drawing to be provided for approval before execution. g. Emergency stop h. Safety catch i. Flashing lights both sides j. In case of power failure condition the High Speed Door should open on UPS Power Supply. k. Door should have the option for manual opening from one side by hand crank l. Bottom Safety edge sensor

Purchase Order No: ATPL/S/16/354
Ref No: UBS/GST/17/253

GENERAL PREREQUISITES AT SITE:

1 Electrical Supply on the site single phase/three phase points at different places at one point per door.
2 Electrical connection for control panel
3 E lectrical cables near to the installation machinery at one point.
4 One room lockable for expensive material /tools/tackles etc., security of which will be in NIHVA Scope.

PRICE SCHEDULE, TERMS & CONDITIONS FOR SUPPLY & COMPLETE INSTALLATION OF THE HIGH SPEED DOORS:

Taxes & Insurance:

Taxes & Duties: GST@18%.
Packing, Freight/ Transport & Insurance: Included

Delivery:

10-11 weeks from the date of confirmed purchase order, advance payment & drawing approval

Payment Terms:

- 50% - Advance along with PO
- 40% - Against receipt of material at site
- 10% - After installation & Commissioning

Warranty/Guarantee:

24 months from the date of installation & commissioning (inclusive of 6 visits at year i.e. 12 visits in 2 years)

Training:

- NIHVA's crew will impart the necessary training to personnel from the Amar tea.
- Also inclusive of lodging, boarding, transportation to and fro.

NOTE:

1. Vendor has taken measurements at site & has quoted accordingly.
2. All site conditions have been checked by vendor before giving final quote & acceptance.
3. All tools/ tackles/cranes/ scaffolding / any other equipment etc. as required for installation & commissioning are in Vendor scope & included in rates.

Purchase Order No: ATPL/S/16/354
Ref No: UBS/GST/17/253

4. Before execution please check once again at site for no of Horizontal or Vertical movement in sectional doors.
5. Before execution actual measurements should be taken at site and the orientation / location should be verified.
6. The maximum design temperature should be considered as per Indian site condition of **50 °C.**
7. It should be considered in design that the conditions are dusty & there will be accumulation of dust. So all panels / covers should be minimum of IP 55 & preferable IP 65.
8. Sectional doors wind resistance to be considered for winds up to speed 60 km & above.
9. Rates are inclusive of Training our team at site for operations / preventive maintenance / maintenance.
10. 3 sets of hard copies of all drawings should be sent to us in Mumbai for approval sign off.
11. **NIHVA** shall ensure and follow all the statutory Government guidelines.

PRICE ESCALATION:

1. Prices quoted herewith in the quotation are firm prices with no escalation due to any reason till the course of contract period.

JURISDICTION:

Any legal dispute arising of the resultant contract will be subject to the jurisdiction of the **Mumbai Courts** in case the same is not settled mutually.

Site/ Delivery/ Billing Address	:	Amar Tea Pvt. Ltd. Plot No. 144/ 3, Raiwadi Road Sanjan, Tal. Umergaon, Dist. Valsad Gujarat – 396 150
GST No.	:	24AAACA3927D2Z7
Contact Person	:	Dr. Pratyush Bhatt
Contact No.	:	+91 8291933755
Email	:	pratyush.bhatt@societytea.com

Thanking you

Yours faithfully
For AMAR TEA PVT. LTD.

DIRECTOR

AMAR TEA PVT. LTD. MUMBAI