QTN No:- SQT/19-20/2617 Dated : 18.06.2020

Kind Attn:- Mr. Nikhil Bakane

Client Name:- **SUROJ BUILDCON PVT. LTD.**

Address :- Bungalow No. 3, Liberty Society Phase-I, North Main Road, Koregaon Park, Pune 411 001, Maharashtra, India.

Email Id:- nbakane@suroj.in

Contact Details:- 020 4135 5926

Dear Sir,

This is with reference to your requirement of Access Cover , we are pleased to quote, competitive rates for ***NIHVA Technologies Pvt. Ltd*** *authorized associated partner of* ***ACO Systems & Solutions (Germany).*** *We hope you find our quotation in line with your requirement. Looking forward for offering better solutions in drainage system.*

Sumerpur UP					
Article No	**Description of Products**	**ACO Description**	**Quantity**	**Price Per Nos**	**Amount**
1.00	**Supply, erection, testing and commissioning of SS304L floor drain in Hygienic design with vertical outlet including inbuilt foul trap seal, S.S. cover plate, S.S.Basket, S.S.strainer, SS Grating with cap and with cement concrete all around the trap or suitable clamps/brackets for high level installation etc. The quote rate shall be inclusive of miscellaneous material consumable etc. complete**	**Hyginic gully 218 fixed height W300 L300 D110 FAT ACO hygienic gully 218 fixed height W300 L300 D110 / D160 ACO silt basket for vertical gully 218, EN1253, 1. Mesh grating W268 L268 E30 / H30, electropolishing**			
	300mm x 300mm x 110mm dia Outlet diameter		2	37,100	74,200
	300mm x 300mm x 160mm dia Outlet nominal diameter		2	41,800	83,600
1.01	**Supply, erection, testing and commissioning of SS304L multi- inlet or plain floor trap with inlet provision, with cement concrete all around the trap or suitable clamps for high level installation etc complete. The quote rate shall be shall be inclusive of miscellaneous material , consumable etc complete. The quote rate shall be inclusive of miscellaneous material consumable etc. complete**	**ACO Multi Inlet Channel With - 300MM x 300MM Wit Centre Outlet Dia 110MM wit Inlet 75MM - (4 Nos) With Mesh grating W268 L268 E30 H30, electropolishing**			
	110 x 75mm dia outlet		8	26,300	210,400
1.02	**Supply, erection, testing and commissioning of Stainless steel SS 316L funnel/ hub drain in Hygienic design with vertical outlet including S.S. cover plate, S.S.Basket, S.S.strainer with cap and with cement concrete all around the trap or suitable clamps/brackets for high level installation etc. The quote rate shall be inclusive of miscellaneous material, consumable etc. complete**	**ACO Turndish For ully Top**			
	100mm nominal diameter		2	15,200	30,400
	150mm nominal diameter		2	17,700	35,400
	300mm nominal diameter		2	23,400	46,800

Article No	Description of Products	ACO Description	Quantity	Price Per Nos	Amount
1.03	**Supply, erection, testing and commissioning of Stainless steel clean out plug as per the drawing and specification with all fittings as required and making good the same etc.. The quote rate shall be shall be inclusive of miscellaneous material , consumable etc. complete**	**SS 200MM x 200MM Cleanout With locked Cover, grating and Sealings - SS 304**			
	75mm nominal diameter	Not Available in desin	4		-
	100mm nominal diameter		3	7,700	23,100
	150mm nominal diameter	Customised Items	2	17,100	34,200
	200mm nominal diameter	Customised Items	2	26,500	53,000
1.02	**Supplying, fabrication, transportation, erection and alignment including installation in position by bolting / welding / screwing of factory made SS 304 trench grating with SS 304 frame over drain trench with all fittings and fixtures, (clips, bolts, self drilling and taping screws, nuts and lock washers) etc., welding, edge preparation, including all labour, material, equipment, handling, transportation, preparation of fabrication drawings, etc., all complete , as per specifications, drawings and instructions of Engineer-in-charge.**	**ACO modular box channel 'Fully compliant to EN 1253** **Fully tested and classifi ed to EN 1433** **Fully pickled and passivated** **Easy and secure telescopic connection with gully** **Adjustable EasyFix levelling feet** **Fully welded end flange to each channel section to allow multi-point clamping of the** **NBR sealing sheet for a totally waterproof connection**			
	150mm Wide (Internal dimension)	1. W155/125 H60/155 - In Slope (Witout Telescopic gully)	100	21,800	2,180,000
	300mm Wide (Internal dimension)	2. W300/270 H60/300 -n Slope (Witout Telescopic gully)	150	33,600	5,040,000
	450mm Wide (Internal dimension)	3.a) W400/370 H60/340 -Slope (Witout Telescopic gully) (Option 01)	200	38,900	7,780,000
		b) 4. W500/470 H60/400 Slope (Witout Telescopic gully) (Option 02)	200	47,100	9,420,000
Total (Rs.)					**25,011,100**

Note :
We don't have Product -
'Supply, erection, testing and commissioning of Cast iron floor clean out plug as per the drawing and specification with all fittings as required and making good the same etc. The quote rate shall be shall be inclusive of miscellaneous material , consumable etc. complete.
'100mm nominal diameter
'150mm nominal diameter
'200mm nominal diameter

1) Qty to be review before the Finalisation of Order

Terms & Conditions :-

1) Transportation Extra.
2) Delivery :10 Weeks from date of confirmed Purchase Order & advance payment.
3) Taxes : GST 18% Extra
4) Validity : 30 Days from Date of Quotation
5) Installation is in your scope. Our Techncian will only guide the installation on site.
6) Unloading of Material at site is in client Scope.
7) Payment Term :- 100 % Advance along with confirmed P.O.

For any further Query please Contact **Mr.Bhavin Jain** on 8551092333.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd