**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**IC-L Construction Consulting Pvt. Ltd**
B-6, Second Floor,
Heritage House "B" Wing,
Ramabai Ambedkar Rd.,
Pune 411 001.

**Date : 06.01.2020**
Quote NO : SQT.19.20.2336
**Kind Attn : Mr. Vivek Shiroor**
Email Id : vivek.shiroor@iclconsulting.in
Contact No: **99 6051 2224**

**Project Name & Location:** Hyderabad, Telangana.

**Subject : Quotation for High Speed Clean Room Door RR300 Clean ,Motorized Rolling Shutter , Fire Rated Rolliing Shutter and Sectional Door.**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **NIHVA ASSA ABLOY High Speed Door RR300 Alu** | 3000 | 3000 | 4 | 632,000 | 2,528,000 | 20,000 | 80,000 |
| 2 | **NIHVA ASSA ABLOY High Speed Door RR300 Alu** | 3000 | 4500 | 1 | 674,000 | 674,000 | 20,000 | 20,000 |
| 3 | **NIHVA ASSA ABLOY High Speed Door RR300 Alu** | 4400 | 3000 | 1 | 680,000 | 680,000 | 20,000 | 20,000 |
| 4 | **NIHVA Make MS Motorised Rolling Shutter** | 3000 | 4000 | 1 | 104,000 | 104,000 | 20,000 | 20,000 |
| 5 | **NIHVA Make MS Motorised Rolling Shutter** | 3000 | 4500 | 2 | 111,000 | 222,000 | 20,000 | 40,000 |
| 6 | **NIHVA Make MS Motorised Rolling Shutter** | 4000 | 4500 | 1 | 138,000 | 138,000 | 20,000 | 20,000 |
| 7 | **2 Hrs Fire Rated Rolling Shutter** | 3000 | 3000 | 2 | 191,000 | 382,000 | 20,000 | 40,000 |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 8 | **2 Hrs Fire Rated Rolling Shutter** | 3000 | 4500 | 1 | 241,000 | 241,000 | 20,000 | 20,000 |
| 9 | **4 Hrs Fire Rated Rolling Shutter** | 3000 | 4500 | 1 | 276,000 | 276,000 | 20,000 | 20,000 |
| 10 | **4 Hrs Fire Rated Rolling Shutter** | 4400 | 3000 | 1 | 266,000 | 266,000 | 20,000 | 20,000 |
| 11 | **Sectional Door** | 2400 | 3000 | 1 | 242,000 | 242,000 | 20,000 | 20,000 |
| | | | **Total** | | | **5,753,000** | | **320,000** |
| | P&F Charges | | | 3% | | **172,590** | | |
| | **Total Without Taxes** | | | | | **5,925,590** | | **20,000** |
| | GST Extra @ 18% | | | 18% | | 1,066,606 | | 3,600 |
| | **Total With Taxes** | | | | | **6,992,196** | | **23,600** |
| | Transportation Charges | | | | | **In Client Scope** | | |
| | Unloading Charges @ Site | | | | | **In Client Scope** | | |

**B) Technical Specification**

| **Specification** | **NIHVA ASSA ABLOY High Speed Door RR300 Alu** |
|---|---|
| **Door construction:** | Certified flexible high performance door, opening in vertical direction, certified for the use in cleanrooms. Compliant to the national norms and regulations in cleanroom applications according to DIN EN ISO 14644-1 and GMP.<br>Certified according to ISO 5 and GMP class C.<br>Low Particle emission , Low Air Exchange.<br>Certified by Fraunhofer |
| **Lintel space requirement:** | 410mm Minimum |
| **Control system incl. self-opening:** | Frequency converter control MCC VectorControl with uninterrupted power supply (UPS) for continuous operation in case of power failure. UPS and MCCVectorControl are installed under the top roll cover.<br>Graphic display and foil keypad for easy operation installed on the drive side. |
| **Door curtain:** | Made of PVC with vertical reinforcement stripes in white (similar RAL 9016). |
| **Speed:** | 2.0 / 1.0 m/s |
| **Power supply:** | 3L/(N)PE 380/400/415/440/480V; 50/60 Hz. |
| **Safety device:** | Pre-running photocell, door line photocell integrated in the side frames, drop down protection in the drive unit. |
| **Protection:** | IP 55. |
| **Self-supporting side frames made of stainless steel V2A:** | Self-supporting side frames max. DW 110 mm, motor cover , top roll cover & bottom profile are in Stainless Steel V2A . |
| **Actuators / Switch:** | Integrated, contactless actuator mounted on Guide rail / side frame. |
| **Drive unit:** | Direct Drive Gear motor, mountable left or right. |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

| Sr .No. | Specification | Motorized Rolling Shutter |
|---|---|---|
| 1 | **Description:** | Motorised Rolling Shutter with MS Laths with thickness of 1 mm. |
| 2 | **Mounting Location area** | Inside area / Outside area |
| 3 | **Mounting Surface** | Side Brackets: Optional = On Concrete /Steel & Side |
| 4 | **Curtain Panel** | The panel made of 1.0mm thick MS. |
| 5 | **Curtain panel size** | 75mm wide |
| 6 | **Curtain Profile** | Curved |
| 7 | **Bottom Profile** | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener |
| 8 | **Side Guide Profile** | M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension) |
| 9 | **Roller Shaft** | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h |
| 10 | **Side Brackets** | MS Plate 3 mm to 10 mm thick, as per the opening dimension. |
| 11 | **Hood Cover** | Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener |
| 12 | **Surface finish** | PU paint or Powder coated |
| 13 | **Drive Unit & Mounting Type** | Indirect Drive, Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection |

| Sr .No. | Specification | Fire Rated Rolling Shutter |
|---|---|---|
| 1 | **Shutter Curtain** | Single Skin Design |
| 2 | **Guide Rail** | G65 powder coated |
| 3 | **Bottom Bar** | 120 powder coated |
| 4 | **Type of Mounting** | Standard |
| 5 | **Motor Drive Unit** | Power Source: 110v 60Hz 1 phase<br>220v 6OHz 1 phase<br>230v 50Hz 1 phase<br>400v 50Hz 3 phase<br>Insulation Class E<br>Manual Chain Override<br>One unit push button switch<br>Gravity drop level<br>Auto close by relay switch after receive of 24vdc fire signal |

| Sr .No. | Specification | Sectional Door |
|---|---|---|
| 1 | **Opening/Closing Speed** | 0.25 m/s |
| 2 | **Door Material** | GI Steel with PUF inside |
| 3 | **Panel Thickness** | 42mm |
| 4 | **Panel colour** | RAL 9002 Powder coated |
| 5 | **External surface of the panel** | diamond grid design with a glossy finish at the section joints. |
| 5 | **Door sealent** | All door sealants made of EPDM rubber. |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333.**

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd