NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0064R1 **Date : 24-11-2017**

Max speciality films ltd
Bhai Mohan Singh Nagar Rail Majra
Nawanshahr Punjab 144533

Kind Attn : **Mr.Sreejith**
Email : sreejith@msfl.in
Contact No : 9878746565

Subject : Quotation for Conveyor System

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	Conveyor 1	1	Set	27,50,000	27,50,000
1	Telescopic Conveyor Make - NIHVA				
2	Fixed Conveyor Make - NIHVA				
3	Take up Conveyor Make - NIHVA				
B.	Conveyor 2				
1	Take Down Conveyor Make - NIHVA				
2	Fixed Conveyor Make - NIHVA				
3	Take up Conveyor Make - NIHVA				
C	Installation Charges For Above				

GST PUNE:	27AAECN0437H1ZM
HSN Code	84289090

Amount in Words	Total Amount	27,50,000
	Rupees Twenty Seven Lacs Fifty Thousand Only	

Technical Specifications :-

SR NO.	Describtion	Specification
A	Conveyor 1 Includes	
1	Telescopic Conveyor Make - Nihva	
	Total Length	17 meter
	Fixed Length	5 meter
	Extended Length	12 meter
	Conveyor width	1 meter
	Control Panel	A fixed main panel with emergency stopper sensor bar, Led lighting
2	Fixed Conveyor Make - Nihva	
	Length of conveyor	8600 mm
	Width of conveyor	650 mm
	Control Panel	For one motor
3	Take Up Conveyor Make - Nihva	
	Length of conveyor	5000 mm
	Width of conveyor	650 mm
	Control Panel	For one motor
B	Conveyor 2 Includes	
1	Take Down Conveyor Make - Nihva	
	Length of conveyor	2850 mm
	Width of conveyor	650 mm
	Control Panel	For one motor
	Motor Rating	0.5 HP
	Max Rpm	250-300 mm/sec
2	Fixed Conveyor Make - Nihva	
	Conveyor length	9500 mm
	Width of conveyor	650 mm
	Control Panel	For one motor
	Motor Rating	1 HP
3	Take Up Conveyor Make - Nihva	
	Length of conveyor	9156 mm with 1 m Base
	Width of conveyor	650 mm
	Control Panel	For one motor
	Motor Rating	1 HP
	MOC for both Conveyor A & B	MS Painted
	Temperature	Ambient

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

2 All structure support is in client scope
3 NIHVA Will provided structure drawing only if required
4 Existing Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Punjab
2	**P & F Charges**	:	NA
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	8-10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	50% advance along with confirm Purchase Order,45% after delivery at your site,100% installation amount after installation & 5% against PBG valid for warranty.
6	**Insurance**	:	Extra if applicable
7	**Tax**	:	GST: 28% on total supply value
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	24 Months from the date of supply &2 visit for service (Accidental damage visit & service charge extra at actual)

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre

7709586333

For Nihva Technologies Pvt Ltd