NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ferrero India Pvt Ltd
IMSOFER Division (Unit I) ,Plot No. F-13,,
M.I.D.C., Baramati, - 413133
Maharashtra, India

Date : 01.10.2019
Quote NO : SQT.19.20.2007R4
Kind Attn : Mr. Amar Ghadage
Email Id : Amar.ghadage@ferrero.com
Contact No: 7888032949

Subject : Revise Quotation for HSD & Steel Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Albany Make Rapid Roll Up Door RR300+AL	2500	5000	1	779,000	779,000	20,000	20,000
2	2 Hrs Fire Door with Sheet Thickness of 1.2mm • Hinges - Yele/Geze make • Door Closure - Yele/Geze make • Vision Window- 200 mm X 300 mm (Glass) • Mortise Dead Lock with Lever Handle	1000	2100	5	35,000	175,000	2,500	12,500
3	2 Hrs Fire Door with Sheet Thickness of 1.2mm • Hinges - Yele/Geze make • Door Closure - Yele/Geze make • Vision Window- 200 mm X 300 mm (Glass) • Mortise Dead Lock with Lever Handle	1500	2200	1	50,000	50,000	5,000	5,000
				Total		**1,004,000**		**37,500**
	P&F Charges			0%		-		
	Total Without Taxes					**1,004,000**		**37,500**
	GST Extra @ 18%			18%		180,720		6,750
	Total With Taxes					**1,184,720**		**44,250**
4	Transportation Charges					**Inlcuded**		
5	Unloading Charges @ Site					**Inlcuded**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA ASSA ABLOY RR300 +

Sr. No	Description	Specifications
1	Door panel:	Transparent PVC with Red (RAL 3002) reinforcement stripes.
2	Barrel:	Aluminium, anodized with shafts made of galvanized steel
3	Wind Reinforcement:	Door Panel wind tabs for improved wind resistance
4	Side Frames:	Aluminium profiles, anodised
5	Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
6	Self-opening:	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.
7	Bottom beam:	Anodized extruded aluminium.
8	Control system:	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s
9	Safety features:	Safety edge, safety photocell (Transmitter/Receiver) inside side columns
10	Push Button	Considered (Both Sides)
11	Motor Cover	Included
12	Hood Cover	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : At Site

Delivery : 4 - 5 weeks for Steel Door & 11-12 Weeks for High Speed Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd