NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Shubhshree Engineering & Constructions Pvt Ltd
Aurangabad

Project, Location : Ranjangaon

Date : 08.03.2021
Quote NO : SQT.20.21.3084
Kind Attn : Manish Sharma
Email Id : manishsharma@shubhshree.co.in
Contact No: 9175575106

Subject : Quotation for Motorized Rolling Shutter, Sliding Glass Door and Turnstile.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorized Single Skin Rolling Shutter**	4000	4500	1	151,000	151,000	20,000	20,000
2	**Motorized Single Skin Rolling Shutter**	3300	4500	1	129,000	129,000	20,000	20,000
3	**Motorized Single Skin Rolling Shutter**	3000	4500	1	122,000	122,000	20,000	20,000
4	**Automatic Sliding Glass Door**	2000	2400	1	193,000	193,000	20,000	20,000
5	**Double Lane Turnstile**	700		5	457,000	2,285,000	20,000	100,000
	Total			**9**		**2,880,000**		**180,000**
6	P&F Charges			3%		86,400		
	Total Without Taxes					2,966,400		180,000
	GST Extra @ 18%			18%		533,952.00		32,400
	Total With Taxes					**3,500,352**		**212,400**
7	Transportation Charges					Extra at atcual		
8	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Slats with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

Automatic Sliding Glass Door

Sr .No.	Specification	Automatic Sliding Glass Door
	POWER DRIVE	
1	**Motor**	High performance and heavy duty DC motor with integrated encoder and gearbox
2	**Power Supply**	170-260 V AC 50-60 Hz
3	**Power Consumption**	170 W
4	**Protection Class**	IP22
5	**Carrying Capacity**	170 Kg for single leaf, 240 Kg for double leaves
6	**Clear Opening**	2,400 x 3,000
7	**Operator Chassis Size**	125 x 168 mm , Aluminium
8	**Carrier Assembly**	Two carrier assembly for each leaf, (2 main and 1 balancing wheel for each carrier assembly)
9	**Trigger Belt**	Special trigger belt design for maximum safety and endurance and minimum noise level
	MICROPROCESSOR	
10	**Working Temperature**	- 20* C + 50* C
11	**Position Selector**	Digital , 6 user positions, LCD touch screen
12	**User Modes**	Auto , Open , In , Out , Locked , Half Opening
		Opening Speed, Closing Speed, Hold Open Time, Half Opening Distance, Opening, Direction, Installer
13	**Installer Settings**	Password, User Password
14	**Obstacle Detection**	Permanent obstacle detection in both opening and closing cycles.
15	**Energy Saving**	Short braking distance during opening and closing cycle for energy saving
16	**Interlocking**	2 doors can be operated using interlocking mode
17	**Resetting**	Can be performed using digital position selector without opening operator cover
18	**Compatibility**	Compatible with fire alarm and access control systems
19	**Fault Monitoring**	Error codes are shown on the digital position selector screen.
	SENSOR	
20	**Safety**	3D infrared curtain photocell
21	**Opening**	Radar
22	**Combiner (Opening + Safety)**	Opening radar with integrated 3D infrared curtain photocell, Energy saving, EN16006
	DOOR LEAF	
23	**Frameless**	With 2 point fittings per door panel
24	**Operator Mounting**	On glass panel provided by others

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorised Full Height Trunstile

Sr .No.	Description	Specifications
1	Framework	304 SS
2	Finishing	Brushed
3	Dimension	(L) 2150 mm x (W) 1500 mm x (H) 2220 mm
4	Pass Width	500 - 700 mm
5	Pass Rate	20 persons/min
6	Operation	Single/Bi-directional
7	Rotor Type	4 arm x 90°
8	Mechanism	Electro-Mechanical
9	Locking	25° from previous rest position
10	Power Voltage	AC 220V +/- 10% 50-60Hz
11	Power Consumption	80W per lane
12	Mode	Fail Safe
13	Operating Temprature	-20°C - 55°C
14	Integration	Any Access control system

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd