WORK ORDER

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Client
Kirpekar Engineering Pvt Ltd
Address:
Kirpekar Engineering Pvt. Ltd. Plant I, Plot No 8A, Raisoni Industrial Park, Hinjewadi MIDC Phase II, A/P MAAN, TAL Mulshi, Dist Pune 411057

PO Number:	430/EL/19-20	W. O. no-	168
PO Dated :	02-03-2020	W. O. Date	07-03-2020
PO Received Date:	07-03-2020	Sales Co ordinator	Varsha
Ref. Quotation:	SQT.19-20.1815R	Front Sales Person	Arjun

Contact Details		Billing Address:	Dispatch Address:
Contact Person:	Balaji Birajdar (purchase)	Kirpekar Engineering Pvt. Ltd. Plant I, Plot No 8A, Raisoni Industrial Park, Hinjewadi MIDC Phase II, A/P MAAN, TAL Mulshi, Dist Pune 411057	Kirpekar Engineering private Limited PLOT No. D-233/3/2, CHAKAN MIDC INDUSTRIAL AREA, PHASE II, AT . POST BHAMBOLI, TAL KHED, DIST. PIJNE - 410501 Maharastrtra, Indla.
Email ID:	purchase@kirpekarengg.com		
Mobile:	77740 11301 / 90288 74633		

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Rate	Amount	Dwg. Approval
1	RP300	Size: (W) 1000 mm X (H) 1200 mm Price: Supply	No	1		-	pending
2	RP300	Installation of above door	No	1		-	

Sr. No	Description	Details
		Albany make Machine Protection Door RP300
1	Door version:	Vertical Rapid Roller Door for machine protection.
2	Side Frames:	Aluminum anodized two parts, to have easy access to switches and service.
3	Door blade:	Curtain RollTexPlus (silicone-free) without window, according to the following RAL colours: blue (RAL 5002),
4	Bottom beam	Aluminium anodized.
5	Drive unit:	Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)
7	Control system:	Controls ACS 50, IP 55 for opening / closing speed approx. 1,0 m/s. Control box painted (RAL 7035) with Up-Stop-Down buttons.
8	Power suppy:	3/(N)/PE 230/380/400/415 V, 50 Hz
9	Safety features:	Safety edge with cable chain integrated in side frames, door line photocell (Transmitter / Receiver) inside side frames, emergency crank and mechanical drop-down protection.
10	Safety limit switch:	1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.
11	Hood & Motor Cover	Albany make

A) Commerical Terms

1)	**Payment Terms:**	50% Advance along with Confirmed Purchase Order & Balance 50% before dispatch
2)	**Delivery Date as per PO:**	within 8 weeks
3)	**Transportation:**	Extra as applicable
4)	**P&F Charges:**	Nil
5)	**Loading:**	NIHVA
6)	**Unloading:**	Client
7)	**Lifting Equipments:**	NA
8)	**Warranty:**	12 months from the date of Installation
9)	**Height arrangement:**	NA
10)	**Electricity Supply:**	Client scope
11)	**GST:**	Extra@18%
12)	**Installation Scope:**	NIHVA
13)	**Mode of import:**	SEA
14)	**HSS:**	NA
15)	**Documentation Required:**	CE certification & certificate of origin, Standard HDR documents

Certified that the above work order finalised in presence of:

	AGM	SALES	PROJECT	PPC	DESIGN	Date & Time
	A. K.	A. P.	P.U.	V. J.	P. A.	