**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**MMC Doortech**
Chennai

**Date :** 23.02.2021
**Quote NO :** SQT.20.21.3050
**Kind Attn :** Mahalakshmi
**Email Id :** jollybanerji@gmail.com
**Contact No:** 9884082122

**Project, Location : Mapal India Green Field Project, Coimbatore**

**Subject : Quotation for Motorized and Manual Rolling Shutter**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


### A) Commercial Offer

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Gear Operated Rolling Shutter** | 2000 | 2500 | 2 | 47,000 | 94,000 | 20,000 | 40,000 |
| 2 | **Gear Operated Rolling Shutter** | 2600 | 2700 | 2 | 57,000 | 114,000 | 20,000 | 40,000 |
| 3 | **Gear Operated Rolling Shutter** | 1200 | 2000 | 1 | 34,000 | 34,000 | 20,000 | 20,000 |
| 4 | **Gear Operated Rolling Shutter** | 3000 | 3000 | 2 | 67,000 | 134,000 | 20,000 | 40,000 |
| 5 | **Gear Operated Rolling Shutter** | 4500 | 4500 | 2 | 124,000 | 248,000 | 20,000 | 40,000 |
| 6 | **Motorized Single Skin Rolling Shutter** | 2000 | 2500 | 2 | 78,000 | 156,000 | 20,000 | 40,000 |
| 7 | **Motorized Single Skin Rolling Shutter** | 2600 | 2700 | 2 | 88,000 | 176,000 | 20,000 | 40,000 |
| 8 | **Motorized Single Skin Rolling Shutter** | 1200 | 2000 | 1 | 64,000 | 64,000 | 20,000 | 20,000 |
| 9 | **Motorized Single Skin Rolling Shutter** | 3000 | 3000 | 2 | 98,000 | 196,000 | 20,000 | 40,000 |
| 10 | **Motorized Single Skin Rolling Shutter** | 4500 | 4500 | 2 | 156,000 | 312,000 | 20,000 | 40,000 |
| | **Total** | | | **18** | | **1,528,000** | | **360,000** |
| 11 | P&F Charges | | | 3% | | 45,840 | | |
| | **Total Without Taxes** | | | | | 1,573,840 | | 360,000 |
| | GST Extra @ 18% | | | 18% | | 283,291.20 | | 64,800 |
| | **Total With Taxes** | | | | | **1,857,131** | | **424,800** |
| 12 | Transportation Charges | | | | | Extra at atcual | | |
| 13 | Unloading Charges @ Site | | | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Gear Operated Rolling Shutter**

| Sr .No. | Specification | MS Gear Operated Rolling Shutter |
|---|---|---|
| 1 | **Description** | Gear Operated Rolling Shutter with MS slats with thickness of 1 mm. |
| 2 | **Mounting Location area** | Inside area / Outside area |
| 3 | **Mounting Surface** | Side Brackets: Optional = On Concrete |
| 4 | **Curtain Panel** | The panel made of 1.0mm thick GI. |
| 5 | **Curtain panel size** | 75mm wide |
| 6 | **Curtain Profile** | Curved |
| 7 | **Bottom Profile** | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener |
| 8 | **Side Guide Profile** | M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick. |
| 9 | **Roller Shaft** | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h |
| 10 | **Hood Cover** | Made of GI Sheet Thickness 0.9 mm GF mm |
| 11 | **Surface finish** | 2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer |
| 12 | **Operation** | Gear Assembly. |

**Motorized Rolling Shutter**

| Sr .No. | Specification | MS Motorized Rolling Shutter |
|---|---|---|
| 1 | **Description:** | Motorised Rolling Shutter with MS Slats with thickness of 1 mm. |
| 2 | **Mounting Location area** | Inside area / Outside area |
| 3 | **Mounting Surface** | Side Brackets: Optional = On Concrete /Steel & Side |
| 4 | **Curtain Panel** | The panel made of 1.0mm thick GI. |
| 5 | **Curtain panel size** | 75mm wide |
| 6 | **Curtain Profile** | Curved |
| 7 | **Bottom Profile** | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener |
| 8 | **Side Guide Profile** | M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick. |
| 9 | **Roller Shaft** | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h |
| 10 | **Side Brackets** | MS Plate 3 mm to 10 mm thick, as per the opening dimension. |
| 11 | **Hood Cover** | Made of GI Sheet Thickness 0.9 mm GF mm |
| 12 | **Surface finish** | PU paint or Powder coated |
| 13 | **Drive Unit & Mounting Type** | Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description |
|---|---|
| 1 | Secured and fully covered Store area to keep the material |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site |
| 3 | Electrical Supply on the site single phase/three phase points at different places. |
| 4 | Any civil / masonry/structural work required |
| 5 | All structure support required |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. |
| 7 | Conduits, Cables required |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

**With Best Regards**
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd