NIHVA TECHNOLOGIES

WEIGHT ESTIMATION SHEET

CLIENT	shree pre fab	DATE	30-03-2024
PROJECT	Cantilever Gate	LOCATION	Pune
FINISH SIZE	8 metre x 5 metre	PREPARED BY	Jayesh

SR	DESC	DETAILS	MATERIAL GRADE	SP.GRAVITY	DIA	WIDTH	HEIGHT	THICKNESS	LENGTH	UOM	QUANTITY	WEIGHT	REMARK
1	10000 mm X 5000 mm)	Tube - Outer Frame	MS	7.85		80	80	3.2	30000	mm	1	232	
		Horizontal Support	MS	7.85		40	40	2.6	10000	mm	1	31	671
		Vertical Support Tube For Slat	MS	7.85		40	40	2.6	4920	mm	7	105	kg
		Corrugated Sheet 4 x 8 feet size (Galvalume Al + Zn 150 gms /sqm sheet)	MS	7.86				0.8		mm	16	304	
2	Top Track	Square Pipe	MS	7.86		100	100	3.2	10000	mm	1	97	
		Guide Roller Assembly	STD							set	5		
3	Accessories	Cantilever Assembly	STD							set	2		
		End Stopper	STD							set	2		
		Electromechanical actuator	STD							set	1		
		Photocells with anodized aluminum vertical mountings.	STD							set	1		
		3 station push Button	STD							set	1		
										Weight For Required Qty	1	769	
										Weight Including Safety Factor	1.5	1153	

Mode Of Operation = Motorised

Motor Required = 1007 kg

Claddding considered from Front Side Only

Reference Image



Cantilever Assembly



Top Track Roller