NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ratnarup Projects Pvt. Ltd
Pune

Date : 18.02.2021
Quote NO : SQT.20.21.3035
Kind Attn : Nilesh Waghmode
Email Id : purchase@ratnarupprojects.com
Contact No: 9657859393

Project Name & Location: Endurance,CHAKAN

Subject : Quotation for NIHVA Make Dock Leveler , Rolling Shutter , Wicket Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer -

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Make Dock Leveler - 6 TON Static Load**	2050	2500	2	235,000	470,000	15,000	30,000
2	**GI 1 mm Thk Single Skin Motorised Rolling Shutter**	6000	7500	3	317,000	951,000	15,000	45,000
3	**GI 1 mm Thk Single Skin Motorised Rolling Shutter**	4500	7500	2	242,000	484,000	15,000	30,000
4	**GI 1 mm Thk Single Skin Motorised Rolling Shutter**	4000	7500	1	216,000	216,000	15,000	15,000
5	**GI 1 mm Thk Single Skin Motorised Rolling Shutter**	3000	6500	2	151,000	302,000	15,000	30,000
6	**GI 1 mm Thk Single Skin Motorised Rolling Shutter**	3000	4500	2	121,000	242,000	15,000	30,000
7	**Wicket Gate with Automation System**	900	2000	1	80,000	80,000	8,000	8,000
8	**Boom Barrier**	6000		1	100,000	100,000	10,000	10,000
9	**Boom Barrier**	8000		1	100,000	100,000	10,000	10,000
10	**Motorized Single Leaf Sliding Gate**	9000	2000	1	412,000	412,000	20,000	20,000
			Total	**16**		**3,357,000**		**228,000**
			P&F Charges	3%		**100,710**		
			Total Without Taxes			**3,457,710**		**228,000**
			GST Extra @ 18%	18%		622,388		41,040
			Total With Taxes			**4,080,098**		**269,040**
			Transportation Charges			**Extra at actual**		
			Unloading Charges @ Site			**In client scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

A-1) Optional Accessories Price List

Sr No	Description	Unit Price / Nos		Sr No	Description	Unit Price / Nos
1	**Radar Sensor**	35000		6	**Pull Cord**	7500
2	**Loop Detector**	35000		7	**Key Switch**	5500
3	**Additional Push Button**	5500		8	**Rubber Bumper**	5500
4	**Interlocking Pull Switch**	20000		9	**Remote**	9500
5	**Smoke Detector**	24000		10	**Flashing Light**	7500
			GST Extra @ 18%		**EXTRA**	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Make Dock Leveler - 6 TON Static Load





Sr .No.	Specification	Specifications
1	**Capacity**	6 Ton Static Load
2	**Dock operation mode**	AC power pack hydraulically operated
3	**Lip operation mode**	Hydraulic
4	**Operation control**	Through panel
5	**Loading platform height from road**	1250mm
6	**Travel above & below dock level**	(+) 300 / (-) 250 mm
7	**Platform Size (W x L)**	2050 mm x 2500 mm
8	**Lip size (W x L)**	2000 x 400 mm
9	**Shut Height**	480 mm
10	**Overall length**	2500mm + Lip Length (400mm)
11	**Maximum slope can be achieved**	10%
12	**Clear Pit dimensions (W x L x D)**	(W) 2100mm x (L)2500 mm x (D)485 mm
13	**Hydraulic power pack**	Standard
14	**Driver type**	Direct by electric Motor
15	**Motor Ratings**	1 H.P
16	**Pump design flow**	2.5 LPM
17	**Pump pressure**	120 bar Operating 200 bar Max.
18	**Safety valve set pressure**	120 Kg/cm²
19	**Pump Type**	Gear
20	**Volume of oil receiver**	7 Lit
21	**No Of Deck cylinder**	2 No
22	**Lip Cylinder**	1 No

GI 1 mm Thk Single Skin Motorised Rolling Shutter





Sr .No.	Specification	GI 1 mm Thk Single Skin Motorised Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1 mm thick .
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 140 mm x 2.5 mm thick
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm
12	**Surface finish**	Powder coated
13	**Drive Unit & Mounting Type**	Indirect Drive, Electric Motor - Direct Mounting - Sprocket chain arrangement
14	**3 Station Push Button**	Included

Manual Wicket Gate

Sr .No.	Specification	Wicket Gate
1	**Door type**	Manual Single Leaf Wicket Gate
2	**Size considered**	Clear opening - (W)900 mm x (H)2100 mm
3	**Mounting Location area**	Inside area
4	**Design Pattern**	Standard Tubular Design Pattern
5	**Outer Frame Tube Sizes**	80 x 80 x 3.2 mm
6	**Internal Vertical Tube Sizes**	40 x 40 x 2 mm
7	**Gap Between Tubes**	100 mm C/C
8	**Painting**	2 Coats of EPOXY polyamide based enamel finish of approved Colour
9	**Operation**	Manually Opening

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	In client scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In client scope
3	Electrical Supply on the site single phase/three phase points at different places.	In client scope
4	Any civil / masonry/structural work required	In client scope
5	All structure support required	In client scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In client scope
7	Conduits, Cables required	In client scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavn Jain on 8551092333**

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd