NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/16-17/0615 **Date : 20.03.2017**

ITC - Agri Business Division
Grand Trunk Road,
Nagarampalem, Guntur,
Andhra Pradesh 522004

Kind Attn : Mr. Kishore
Email : D.Kishore@itc.in
Contact No : 8978483409

Project Name And Location : ITC, Guntur

Subject : Quotation for Sachet bagging solutions Secondary & Tertiary Packing for End of Line Automation

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication.
Please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
1	Secondary & Tertiary Packing of Sachet Pouch String – Up to 10 pouches/min only.	1	No.	3,950,000.00	3,950,000.00
2	Installation, Commissioning & Site Supervision	1	No.	130,000.00	130,000.00
	Total				**4,080,000.00**

VAT TIN :	27545250455 V		**TOTAL BASIC AMOUNT**	**4,080,000.00**
CST TIN :	27545250455 C	**Amount in Words :**	**Rupees Forty Lakh Eighty Thousand Only**	
Service Tax No:	AAECN0437HSD001			

A **REQUIREMENT:**

Secondary & Tertiary Packing – For Up to 10 Secondary Pouches/Min

1 String MAT transfer inclined conveyor & collation.
2 Packing of collated string MAT into LDPE bags, transfer through cleated conveyor to pick fill seal machine.
3 Check weigher for LDPE bag
4 Packing of LDPE bags in to HDPE bag.
5 Portable stitching machine for HDPE bag.
6 Product/pouch dimension - 100mm X 80mm (8gm pouch)
7 4 head FFS machine in which string MAT of 1X10 i.e. 10 or 5 pouches are coming out from single chutes.
8 Pouch variants weight – 8, 10, 12, 20 gm.
9 MAT L * W * – Customer to confirm
10 Total speed of the machine is 100PPM X 4 i.e. 400PPM maximum for 8gm pouch
12 In one LDPE bag 6 or 5 MATS will be packed
13 Automated leaflet insertion in LDPE bag
14 LDPE bag dimension – 355mm X 300mm
15 HDPE bag dimensions -
950mm X 350mm X 200mm (Gusseted) (10, 50, 100 & 200gm variants)
1130mm X 350mm X 200mm (Gusseted) (Turmeric powder)

B SCOPE OF SUPPLY:

I LDPE bag packing machine consisting of below units for 8, 10, 12, & 20GM POUCHES ONLY & FOR UP TO 10 PS/MIN.

1 Take up conveyor.
2 Cleated conveyor for collated strings
3 LDPE bag packing machine - Pick fill seal machine
4 Check weighing unit with rejection system for LDPE bags.

II HDPE bag packing machine consisting of below units for 8, 10, 12, & 20gm pouches only.

1 Conveyor for packed LDPE bag
2 LDPE bag counting & hopper dumping system
3 Manual loading of HDPE bag.
4 Stitching machine for HDPE bag.

C LIST OF BOUGHT OUT ITEMS:

1 PLC and 5.7" HMI- AB
2 Pneumatics: Festo.
3 Motor and Gearbox: Bonfiglioli
4 MOC: MS painted/ Powder Coated.
5 Bearings: SKF.
6 Control panel: MOC MS.
7 Air pressure at site required 5 to 7 bars.
8 Flow wrap system
9 Portable stitching machine – Revo

D SEQUENCE OF OPERATIONS

1 Input to the system will be vertically dropped strips at 100PPM from 1 head We will receive string MAT of 1X10 i.e. 10 pouches from one output chute.
2 These strings will be conveyed using take up conveyor to turn table
3 The strings are manually collated and dropped into cleated conveyor The required strings are dropped into a single cleat A leaflet is manually inserted along with the strings.
4 The cleat conveyor transfers the string to pick fill seal system for packing into LDPE bag
5 At the end of pick fill seal system the LDPE bag is weighed on checkweigher system before feeding into HDPE bag.
6 LDPE bag counting is done before dumping into hopper for HDPE bagging
7 The HDPE bag - operator will load a empty bag to hopper unit & counted LDPE bags are transferred into HDPE bag
8 HDPE bag is stitched manually.

E SCOPE OF WORK:

1 Machine Design & manufacture
2 Assembly
3 Trials
4 Commissioning
5 Training

F CUSTOMER SCOPE

1 Consumables
2 Air piping & air source,
3 Input power supply to the control panel.
4 All civil work & foundation,
5 Unloading on site & storing of materials on receipt will be customer's responsibility.
6 Material handling equipments at the site
7 Samples of all variants: FOC to our plant for trials

Terms & Conditions

1	**Price**	:	Ex Works Pune
2	**P & F Charges**	:	Extra 3 %
3	**Freight Notes**	:	Extra at actual
4	**Delivery**	:	13-15 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing
5	**Payment**	:	60% advance agaisnt PO + 100% taxes against delivery at site 40% deliver of installation against installation & commissioning
6	**Insurance**	:	Extra As applicable
7	**Sales Tax**	:	Extra as applicable at the time of dispatch. Presently @13.5% VAT (supply withing Maharshtra OR
8	**Service Tax**	:	Extra @ 15%
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to contact **Mr.Mayur Derle** on 7709209333 For any further Clarification /Information in this concern.

With Best Regards

Monika Kidgaonkar

020-66304033 / 8551091333

For Nihva Technologies Pvt Ltd