NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/20-21/2686 **Date : 10.09.2020**

Freshlink Agro Cold Storage Pvt.Ltd.
Pune

Kind Attn: Mr.Jayant Joshi
Email: freshlinkcs7@gmail.com
Contact No: 8530919955

Project Name And Location : Fresh Link Agro Cold Storage Project

Subject : Quotation for Telescopic Conveyor, Belt Conveyor and Goods Lift

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Crate Lifter Conveyor** **(Supply + Installation)**				
	Technical Specifications : • Conveyor Type : Crate Lifter • Chain Dimond/equivalent • Foot Spectra make (polymide) • Bearing NTN/ equivalent • Conveyor speed : 6 mtr/min • Gear motor make Bonfiglioli • Conveyor Height : 13 mtr • Conveyor length : 15000 mm • UHMWPE make Spectra • Contact part MS powder coated • Non contact part MS powder coated • Electrical item Delta/equivalent • Lifter plate size : (L) 550mm x (W) 400 mm • Direction : Forward/Reverse	1	No	692,000	692,000
B	**Modular Belt Type Conveyor** **(Supply + Installation)**				
	Technical Specifications : • Conveyor Type : Modular belt type • Belt make Spectra • Gear motor make Bonfiglioli • Bearing NTN/ equivalent •Foot Spectra make (polymide) • Conveyor speed : 8 mtr/min • Gear motor make Bonfiglioli • Conveyor height 750 mm • Conveyor length : 15000 • UHMWPE make Spectra • Contact part MS powder coated • Non contact part MS powder coated • No. of conveyor 10 nos. • Electrical item Delta/equivalent • Height adjustable +/- 50 mm	1	No	425,000	425,000
C	**Goods Lift** **(Supply + Installation)**				
	Technical Specifications : • Capacity : 2500 Kgs • Speed : 0.25 M/S • CAR TRAVEL : G + 4 • NO OF STOPS : 5 • NO OF OPENING : 5 • Landing Door Finish : Manual Door Collapsable • CAR Door Finish : Manual Door Collapsable • Door Opening Size : 1200 mm • CAR Size : (W) 1600 mm x (Depth) 2000 mm • CAR Finish : MS Powder Coated • CAR Flooring : MS Plate • Elevator Rope : USHA Martin (Dual Strength) • Elevator Well : 1800 MM WIDTH, 2500 MM DEPTH (INSIDE FINISHED) • Elevator Pit : 500 mm Depth	1	No	2,000,000	2,000,000
D	**Telescopic Conveyor** **(Supply + Installation)**				
	Technical Specifications : • Conveyor Type : Telescopic • Total length of conveyor : 12000 • Collapsed length: 5000 mm • Telescopic Length: 7000 mm • Width Of Conveyor : 1350 mm • Width Of Conveyor Belt : 600 mm • Conveyor Capacity: 30 kg / mtr • Conveyor length : 15000 mm • Speed:30 mtr / min (Variable speed) • Drive Type : • Conveying : Auto/ Manual • Telescopic: Auto/ Manual	1	No	1,197,000	1,197,000
	Total				**4,314,000**

GST Pune	27AAECN0437H1ZM	**TOTAL BASIC AMOUNT**	**4,314,000**

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material.
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	3 % Extra as applicable
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order and Balance before Dispatch.
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	GST Extra as applicable
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to contact **Mr.Vijay Tarak - 8551093333** For any further Clarification /Information in this concern.

With Best Regards

Smita Khare
9673991333
For NIHVA Technologies Pvt Ltd