Budgetary Offer

Name of Work: - Provision of tyre killers & bollards at Kangra Airport

Sr. No.	Description of Items	Unit	Qty	Rate	Amount
1	Design, Supply, Installation, Connection, Testing and Commissioning of K4 crash rated electro-hydraulic stainless steel (SS 304) blocking bollard system operatable on AC power supply for following set of Bollard: (i) Each bollard shall have blocking height: 750 - 900 mm, diameter: 220 - 275 mm provided with in-built LED lightning on top circumference of bollard as per PAS 68 or equivalent standard and shall bear an impact load not less than 110 kN. (ii) The system shall suitably control multiple units with one common drive unit with operation time not more than 8 seconds and shall be capable of performing atleast 200 full cycles per hour and also having manual operation through hand pump in case of power failure performing atleast 3 full cycles. (iii) The system shall have all other accessories like safety interlock detector, sump pump, hydraulic power unit, control and logic circuit etc. complete as required as per the specification mentioned in Tender Document. (iv) The scope of work also includes all civil works such as construction of suitable RCC/PCC support structure to make withstand of bollard against crash rating as per OEM including cutting of bituman /PCC road /removing of Paver block and refixing manually/ by mechanical means for suitable width and depth, disposal of material as per direction of engineer in charge, repair and making good the same etc. complete as per site requirement and meeting the technical specifications. (K4 crash rating test certificate from accredited authority shall be submitted by bidder)	Job	3		
	Minimum 6 Set Bollard For Exit Gate (Blocking upto 6.0 meter)				
2	Design, Supply, Installation, Testing and Commissioning of Fixed Type K4 crash rated, stainless steel (SS 304) Bollard of blocking height 750 - 900 mm, diameter 220 - 275 mm, having impact load minimum 110 kN including all civil works construction of suitable RCC/PCC support structure to make withstand of bollard against crash rating as per OEM including cutting of bituman /PCC road /removing of Paver block and refixing manually/ by mechanical means for suitable width and depth, disposal of material as per direction of engineer in charge, repair and making good the same etc. complete as per site requirement and meeting the technical specifications. (K4 crash rating test certificate from accredited authority shall be submitted by bidder) .	Job	2		

3	Design, Supply, Installation, Connection, Testing and Commissioning of Crash-Rated Electro-Hydraulic / Electromechanical flat type Tyre Killer (upto 6 Metres Length Blocking Width) made of heavy duty M.S. Steel consisting of hardened steel tyre killer spikes of suitable thickness at height of 450 mm from ground at an angle of 60 degree to withstand heavy impact with closing / opening time 2-3 Seconds and suitable to operate on AC power supply alongwith complete control panel, safety and protections accessories etc. including laying of suitable size cable from Power Supply Panel to Motor Control Panel, Green & Red Traffic Lights, Radio transmitter Receiver Unit, Provision of lowering in case of power failure and all required accessories including all civil works construction of suitable RCC/PCC support structure to make withstand of bollard against crash rating as per OEM including cutting of bituman /PCC road /removing of Paver block and refixing manually/ by mechanical means for suitable width and depth, disposal of material as per direction of engineer in charge, repair and making good the same etc. complete as per site requirement and meeting the technical specifications.	Job	2		
				TOTAL (A)	
CMC Charges for 03 years after difect liability of 02 years					
				CMC Charges for 1st Year	
				CMC Charges for 2nd Year	
				CMC Charges for 3rd Year	