NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Sawant grop of Industries
Pune

Date : 14.09.2019
Quote NO : SQT.19.20.2066R
Kind Attn : Mr. Vinod Sawant
Email Id : saindustries2009@rediffmail.com
Contact No: **9860954277**

Project Name & Location: Sawant group of Industries, Chakan

Subject : Revised Quotation for Sliding Gate, Wicket Gate & Sliding Glass Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	A. Motorised Single Leaf Sliding Gate	5800	1900	1	335,000	335,000	-	Inclusive
2	Wicket Gate	900	1900	1	35,000	35,000	-	Inclusive
3	Wicket Gate	950	1900	1	35,000	35,000	-	Inclusive
4	Besam Sliding Glass Door	2850	2000	1	245,000	245,000	-	Inclusive
				Total		**650,000**		
				Total Without Taxes		**650,000**		**-**
				GST Extra @ 18%	18%	117,000		-
				Total With Taxes		**767,000**		**-**
6	Transportation Charges					**In Client Scope**		
7	Unloading Charges @ Site					**In NIHVA Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorised Sliding Gate	
Door type	Motorized Sliding Gate
Clear Opening gate dimension	5800mm (W) x 1900mm (H)
Opening Direction	Horizontal - from left to right or reverse
Mounting Location area	Inside area
Design Pattern	Standard Tubular Design Pattern
Outer Frame Tube Sizes	72 x 72 x 3.2 mm
Internal Vertical Tube Sizes	40 x 40 x 2 mm
Gap Between Tubes	125 mm C/C
Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chrome plated)
Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
Painting	2 Coats of EPOXY primer and 2 coats of Synthetic enamel paint
Emergency Operation	Manual after turn the switch
Telescopic Mechanism	Inbuilt with Gate
Operating Switch	Push Button from inside
Safety	Photocells, Flashing Light
Metal Rack	zinc plated metal rack
Installation Checks	need to be check = space requirements + substructure + Mounting access + Access in the event of power cut

Sliding Glass Door
ASSA ABLOY-BESAM-Automatic Sliding Door SL 500
100% imported from Sweden
Specifications :
1. Main power supply
2. Operator type- Bi part operator.
3.Glass : 10mm thick toughened glass

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 4 - 5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance received without GST, Confirmed Purchase Order & 20% Balance before dispatch.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Vivek
853037333
For NIHVA Technologies Pvt Ltd