RMK INFRASTRUCTURE PVT. LTD.

Ref: RMK/WO /2020/ 182 -B **Date :- 02/09/2020**

Name of contracting firm :- NIHVA Technologies Pvt. Ltd.

Name of firm owner :- Mr. Arjun Patil

Site :- Nidar-Cooper Shed, Navlakh Umbre Talegaon dabhade, Pune.

Work specialization :- Manual Rolling Shutter

Annexure- 'B'

Sr no.	Item Description	Unit	Quantity	Rate	Amount
A	**Rolling Shutter- Design, Supply & Installation**				
1	**Manual Rolling Shutter** **Technical Specification:-** **1 Description :-** Gear Operated Rolling Shutter with MS Laths with thickness of 1 mm. **2 Mounting Location area :-** Inside area / Outside area **3 Mounting Surface :-** Side Brackets: Optional (On Concrete) **4 Curtain Panel :-** The panel made of 1.0mm thick MS. **5 Curtain panel size :-** 75mm wide **6 Curtain Profile :-** Curved **7 Bottom Profile :-** M. S. Plate 100 mm x 2.5 mm thick with angle stiffener **8 Side Guide Profile:-** M. S. " U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension) **9 Roller Shaft :-** M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia -100 to 300 mm as per w x h **10 Hood Cover :-** Made of MS Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener **11 Surface finish :-** 2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat **12 Operation :-** Gear Assembly.				
1.1	Manual Rolling Shutter Clear opening 2000mm wide x 3600 mm tall (As per Approved RAL Code from both sides,Location:- @ Production Building R Grid (Mechanical Production)	NOS	1.00	53,500	53,500
				Total	**53,500**

Note: The rate is inclusive of all taxes, Government Levies, all statutory compliances, Taxes and Charges of local authorities etc. complete. Only GST will be paid as extra same should worked out as per antiprofitering clause of GST.

Delivery : 15 days from the date of shop Drawing approval.

Warranty for mechanical & electrical parts with maintenance of shutters is for 12 Months.

*	Condition of work order are same as per the reference RMK/WO /2020/ 182 dated 18-06-2020, Safety & Environment requirements, statutory requirement, commercial terms, Special Condition & payment conditions.

I have read all the above terms &condition and are accepted to me.

For, NIHVA Technologies Pvt. Ltd. **For, M/S.RMK INFRASTRUCTURE PVT.LTD.**

Authorized signatory

Coordinator Nisar | **Billing** Gunjan | **Tender** Sachin | **Auditor** R. Patel | **Authorized signatory** Mohan Kharche / RRK Sir