NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Patvin Engineering Private Limited
Patvin House, W-193, TTC Industrial Area,
MIDC Khairane, Navi Mumbai - 400 709

Date : 17.10.2020
Quote NO : SQT.20.21.2668 R1
Kind Attn : Mr. Ganesh Thopate
Email Id : proposals@patvin.co.in
Contact No: **8108272794**

Subject : Quotation for Fire rated Sliding Door at Maruti Suzuki Plant

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2, 3, 4
C.	General Conditions	5
D.	Terms & Condtions	5

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Fire Rated Sliding Door	1880	2200	1	125,000	125,000	Inclusive	
				Total		**125,000**		-
				P&F Charges		-		
				Total Without Taxes		**125,000**		-
				GST Extra @ 18%	18%	22,500		-
				Total With Taxes		**147,500**		-
				Total Supply + Installation with Taxes				**147,500**
2	Transportation Charges				**In Client Scope**			
3	Unloading Charges @ Site				**In Client Scope**			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Fire Rated Sliding Door

Sr. No	Description	Specification
1	Door type	Fire Resistant Door Fusible link (Rated for 68 deg. C based Auto Sliding type (2 hours fire rated)
2	Door Diemension size	2080mm (W) x 2300mm (H)
		As per the norms an overlapping of 100 mm in height and 200 mm in width is considered while calculating the sizes of the doors and is mandatory to restrict fire from escaping from the gaps between the wall and the shutters. This door is always kept into open position and at the time of fire break, fusible link melts which allows the counter weight hung to the wire rope to pull the panel automatically close and to prevent fire from spreading further. Standard accessories are included in the supply.
3	Accessories Included	Fusible link, wire rope, guide rail, counter weight, pulleys as per BS 476, Part 20 & 22 and standard accessories included
4	Glass	Not Considered

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd