NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0011R **Date : 14-07-2017**

Hindustan Unilever Ltd
Vadamangalam NH 45
Pondicherry - 605001

Kind Attn : Mr. Ashish Tripathi
Email : ashisht@corbus.com
Contact No : 7574853412

Subject : Quotation for Access Control System

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
1	**Access Control System with Bluetooth**				
	Technical Specifications				
A]	**Tripod Arm**				
1	Model number- TS 2000	6	EA		
2	Application - Outdoor				
3	Design Housing Variant - Short				
4	Passage Width - 515 mm				
5	Drive Technology -Magnetic MHTM				
6	Voltage - 110-240V AC, 50/60Hz				
7	Power Consumption - 60W / 65W				
8	Dimension - 400x300x1035 mm / 260x1300x1035 mm				
9	Enclosure Rating - IP 44				
10	Weight - 40 kg / 60 Kg Approx				
11	Temperature - upto 50 deg.				
2	**Installation Charges For Above System**				
B]	**Biometric Reader**				
1	Platform -Leading edge optical based sensor technology	12	EA		
2	software- SQL database / SQL, .NET, Windows				
3	Finger print Templates- 1500 / 16000 nos				
4	Transaction database -24000 / 100000				
5	Enclosure Rating - IP65 Weather proof				
6	CPU - ARM9, 400 MHZ / 3.0 GHZ				
7	Memory -32MB NOR, 64MB DDR ram / 8Gb Ram, 120GB Hdd				
8	Power Consumption - 12V, Max 400 mA (4.8 W) / 12V, Max 350mA				
9	Dimension - 58x191x62 mm / 190x105x115 mm				
10	RFID card Options -125KHz EM/ 13.56 MHz Smart card				
3	**Installation Charges For Above System**				
C)	Server Architecture based Time Attendance Software	1	EA		
4	**Installation Charges For Above System**				
D)	mifare card	1500	EA		
5	**Installation Charges For Above System**				
E)	desktop for software	1	EA		

GST PUNE:	27AAECN0437H1ZM
GST GUJRAT:	24AAECN0437H1ZS

Total Supply Value (Final Prices)	**19,34,050.00**
Total Installtion Value	**1,00,280.00**
Total Value	**20,34,330.00**
18% GST On supply value	**3,66,180.00**
Total Amount	**24,00,510.00**
Amount in Words	**Rupees Twenty Four Lacs Five Hundred & Ten Only**

Note : Prices of below items upto 30mtrs are inclusive in above prices, and below are the extra charges for more than 30 mtrs

Sr.No	Description	Qty	Unit	Rate In INR
1	Supply and installation of 25mm PVC conduit,T,Bend,shadel & complete accessories	1	Mtr	65.00
2	Supply Installation Testing & Commissioning 8CX0.75-U-U-ABC-P-CABLE	1	Mtr	90.00
3	Supply Installation Testing & Commissioning Flexible cable 3X1.5 Sqmm power Cable	1	Mtr	60.00

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1. **Price** : Ex. Works Pondichery
2. **P & F Charges** : NIL
3. **Freight Notes** : Extra Rs. 75,000/-
4. **Delivery** : 9 -10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5. **Payment** : **80% advance along with confirm Purchase Order & balance before dispatch**
6. **Insurance** : Extra if applicable
7. **Tax** : GST: 18% included in above price
8. **Validity** : Validity of Offer is 15 days from the of quotation
9. **Warranty** : 12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre
7709586333
For Nihva Technologies Pvt Ltd