FLOOR MOUNTED SCISSOR LIFT WITH ROLLER TOP

CAPACITY - 200KG

PLATFORM SIZE-800WX1000L

CLOSE HEIGHT - 400 MM

MAXIMUM HEIGHT - 1250 MM

LIFT HEIGHT -850 MM

FEATURES - HYDRAULIC LIP ON ONE SIDE &
SAFETY RAILING OF HEIGHT 500 MM ON TWO SIDE
LIMIT SWITCH FOR MAXIMUM LIFT

SR NO	ITEM	DESCRIPTION	COST
1	FABRICATION COST	M.S. RAW MATERIAL WEIGHT - 300 KG	25500
2	POWERPACK	1 HP , 1.8LPM , 5 LITRE TANK	25000
3	CONTROL PANEL	1 HP	6000
4	HYDRAULIC CYLINDERS	1 NO OF CYLINDER BORE 30 MM STROKE 300 MM	7000
5	HOSES & CONNECTOR	STD AS PER REQUIRED	7000
6	HYDRAULIC OIL	STD AS PER REQUIRED	1500
7	ELECTRIC CABLES	STD AS PER REQUIRED	2500
8	MACHINING & PLATES	STD AS PER REQUIRED	6400
9	PAINTING	4 LITRE APPROX.	3300
10	MISCELLANEOUS	LABELS , ETC	1000
11	INTERNAL TRANSPORT		1000
12	ROLLER	DIAMETER 50 , L-800 , 10NOS	7000
		MANUFACTURING COST IN INR	93200

PREPARED BY - SIDDHESHWAR SHELAKE