NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1911R **Date : 07.08.2019**

ImpelPro SCM Solutions Pvt. Ltd.
407, MINT, Behind Hiranandani Meadows,
Thane - 400 610. I +91 22 2173 9741/42

Kind Attn : Mr.Sudhir Dabke
Email : sudhir@impelpro.in
Contact No : 8355 97 8344

Project Name And Location :ImpelPro SCM Solutions Pvt. Ltd.

Subject: Quotation for High Speed Door HS9010PFR, Sectional Door, dock Leveller, Sliding Door.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**ASSA ABLOY Make High Speed door HS9010PFR** **(Supply + Installation)**				
Area of use:	Inside				
Material:	Galvanised steel				
Colours:	8 standard colors - white, yellow, green, orange, red, gray, black, blue				
Safety:	1) Photocells in side columns 2) Flexible soft bottom edge including wireless edge activator 3) Break-away and self-repair function				
Vision Window	Single row with 400 mm Height				
Operating speed:	Opening: up to 2,4 m/s ** Closing: 1,2 m/s				
Wind load resistance:	Class 1 (300 Pa (N/m²)				
Water penetration:	Class 1 (30 Pa (N/m²))				
Air permeability:	Class 1 (24 m³/m²/h at 50 Pa)				
Thermal transmittance:	6,02 W/(m²K)				
Lifetime expectations:	1.000.000 cycles				
Temperature working range:	-30°C +5°C				
1	**Size:(W) 2100 mm x (H) 4400mm**	1	No	1,023,000	1,023,000
	Installation	1	Nos.	20,000	20,000
Total					1,043,000

B	**ASSA ABLOY-ALBANY Sectional Door** **(Motorised Sectional - Vertical Lift with 2 windows,** **motor & control,** **bottom safety edge and with all safety features ,** **Opening/Closing Speed - 0.25m/s)** **Panel Thickness - 42mm** **Panel Inside insulation metrial -Insulation material to be CFC free polyuretane foam.** **Water Penetration - EN 12425 class 3** **Air Permealibity - EN12426 class 2** **Wind Load - EN21424 class 3** **Thermal Transittance - EN 12428 1.10W /m2K** **Vision window at comfortable height** **Interlocking With Dock leveller**				
1	Size : (W) 2500 mm x (H) 3000 mm	6	No	332,000	1,992,000
	Installation	6	Nos.	20,000	120,000
Total					2,112,000

C	**Dock Levelers (NIHVA Make)** **2 cylinder for Deck & 1 cylinder for LIP Operator by Standard Control Panel (Deck Up / Down / Lip Up / Down)** **Rubber Bumpers comply with EN 1398 Standards.** **Leveller platform - single piece plate with antiskid chequered surface.** **Operating limit - minimum (+) 300mm and (-) 150mm with reference to dock/floor level** **Lip Length - 400mm antiskid chequered plate.** **• LED Dock Light** **• Vehicle communication light system-Dock area** **• Wheel Chocks with Chain**				
1	**Dock Levelers Capacity -6 Ton Point Load.** Size: (W)2000mm x (L)2500mm	6	No	250,000	1,500,000
	Installation	6	Nos.	15,000	90,000
	Total				1,590,000
D	**Automatic Single Leaf Sliding Door** **Supply of Double leaf Manual Sliding Door with 80/120 mm thickness (Density 42kg/m3) with 0.6 mm PPGI , ALU. Wall Frame (3.5 mmthick), Heavy duty Aluminium Track, Aluminium Door Profile , SS 304 Door Opener & Closure,with Pull Cord ,FDA Approved Gasket, Cladding , Canopy , SS 304 Integrated Pad Lock arrangement Rollers: - The rollers are made of POM (nylon). The roller brackets, the stud bolt the washer and the nuts are made of SS. For 120 mm thickness Heating Arrangement: - Supplied with heating cables in both frame / threshold and door blade. The threshold which is manufactured of anodized aluminium is to be placed into the floor. Alternatively, the door can be upplied without a threshold, if supplied with extra heating at bottom of the door blade.**				
SD1	(W) 2100 x (H)4400 mm , Door Thickness 80 mm	4	No	406,000	1,624,000
SD2	(W) 2100 x (H)4400 mm , Door Thickness 80 mm	1	No	406,000	406,000
SD3	(W) 2100 x (H)4400 mm , Door Thickness 120mm	4	No	462,000	1,848,000
SD4	(W) 2100 x (H)4400 mm , Door Thickness 80 mm	1	No	406,000	406,000
	Optional Accessaries - Remote	10	No	10,000	100,000
	Installation	10	Nos.	15,000	150,000
	Total				4,534,000
E	**Insulated emergency exit door, manual**				
E1- A-1	1000 (W) X 2100 (H)	1	No	50,000	50,000
	Installation	1	Nos.	15,000	15,000
	Total				65,000

F	**Insulated hinged door,manual** **Supply of Single leaf and Double leaf Hinged Door with 80 mm thickness for Positive temp. (Density 42kg/m3) 0.6 mm PPGI sheet, FDA** **Approved Gasket, Cladding , emergency unlocking arrangement form inside,**				
D1a- A-2	(1000 x 2100 mm) , Door Thickness 80 mm	1	No	45,000	45,000
D1b- A-1	(1000 x 2100 mm) , Door Thickness 80 mm	1	No	45,000	45,000
D1c- A-1	(1000 x 2100 mm) , Door Thickness 80 mm	1	No	45,000	45,000
D2- A-1	(1000 x 2100 mm) , Door Thickness 80 mm	1	No	45,000	45,000
	Installation	4	Nos.	10,000	40,000
Total					220,000
G	**Insulated hinged door,manual** **Supply of Double leaf and Double leaf Hinged Door with 80 mm thickness for Positive temp. (Density 42kg/m3) 0.6 mm PPGI sheet, FDA** **Approved Gasket, Cladding , emergency unlocking arrangement form inside,**				
D3- Quarantine	(1800 (W) X 2100 (H)) , Door Thickness 80 mm	2	No	55,500	111,000
	Installation	2	Nos.	12,000	24,000
Total					135,000
H	**Assa Abloy Make Dock Shelter** **Rectractable Dock Shelter** **(100% Imported products from Europe)** **Top & Side Curtaiins - Double Layer High Quality Polyester** **Thickness - 3.0 mm**				
1	**Size: (W) 3250 mm X (H) 3200 mm** **(Supply & Installation)**	6	Nos.	135,000	810,000
	Installation	6	Nos.	15,000	90,000
Total					900,000
I	**Transportation**				
1	**For All Doors**				**50000**

GST Pune :	27AAECN0437H1ZM	**Total**	**10649000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex Works Pune
2	**P & F Charges**	:	@3 % of total supply value
2	**Delivery**	:	10-12 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
3	**Freight**	:	Mention Above.
3	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch
4	**Insurance**	:	Extra As applicable
4	**Validity**	:	Validity of Offer is 15 days from the date of quotation
5	**Warranty**	:	12 months from the date of supply

If there is any query please feel free to contact Mr. Ravindra Kharat on 7410169333.

With Best Regards
Ulka Auti
7219206333
For Nihva Technologies Pvt Ltd