**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Bridgestone India Private Limited**
Plot No. A43, Phase-II, MIDC Chakan, Village Sawardari
Khed taluka, Maharashtra 410501

**Date :** 01.04.2021
**Quote NO :** SQT.20.21.3036 R
**Kind Attn :** Neha Karve
**Email Id :** neha-karve@bridgestone.co.in
**Contact No:** 9730368018

**Subject : Revised Quotation for Assa Abloy Make HSD RR300+Al**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **ASSA ABLOY Make High Speed Door RR300+Alu (Supply + Installation)** | 4000 | 4000 | 3 | 675,000 | 2,025,000 | **Included** | |
| | | | | **Total** | | **2,025,000** | | - |
| | P&F Charges | | | 3% | | **Included** | | |
| | **Total Without Taxes** | | | | | **2,025,000** | | - |
| | GST Extra @ 18% | | | 18% | | 364,500 | | - |
| | **Total With Taxes** | | | | | **2,389,500** | | - |
| | **Transportation Charges** | | | | | **Included** | | |
| | **Unloading Charges @ Site** | | | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**ASSA ABLOY Make RR300+Alu**



| Sr. No | Specification | ASSA ABLOY Make Rapid Roll Up Door RR300+Alu |
|---|---|---|
| 1 | **Description** | Flexiable High Performance Door , Opening in vertical direction for interior use in wind protected area |
| 2 | **Side Frames** | Made of Aluminium |
| 3 | **Door Curtain** | Made of transparent PVC with Fabric reinforcement stripes Red (similar to RAL 3002). |
| 4 | **Top Roll** | Made of Anodized Aluminium |
| 5 | **Opening / Closing Speed** | up to max. 1.2 / 1.2 m/s. |
| 6 | **Wind load resistance** | class 1 (EN 12424) up to DH = 3500 mm, class 0 (EN 12424 at DH> 3500 mm |
| 7 | **Control System** | MCC Vector Control |
| 8 | **Drive unit:** | Hollow shaft gear motor. |
| 9 | **Bottom profile** | anodized aluminium. |
| 10 | **Protection** | IP 55 |
| 11 | **Safety:** | Electrical safety contact edge |
| | | Evaluation via integrated cable chain |
| | | Door line photocell in the side frames |
| | | Drop down protection by integrated balancing system |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : FOR site Delivery

**Delivery** : 10-12 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 30 days Credit .

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

**With Best Regards**
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd