NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Denasa Buildcon
C-3, Sant Tukaram Vyapar Sankul, First Floor
Sector 24, Pradhikaran, Nigdi, Above Hotel Savali,
Pune - 411044.

Date : 24.05.2021
Quote NO : SQT.20.21.2738R3
Kind Attn : Mahesh Pawar
Email Id : mahesh.p@denasaindia.com
Contact No: 8308810541

Project Name & Location: Vedal, Tamilnadu

Subject : Quotation for Motorised Rolling Shutter, Dock Leveler, Dock Shelter and Sliding Glass Door.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorized Rolling Shutter	5000	6000	2	203,000	406,000	10,000	20,000
2	Motorized Rolling Shutter	3000	4000	4	101,000	404,000	10,000	40,000
3	Automatic Sectional Door Vertical Lift	3000	4000	19	198,500	3,771,500	10,000	190,000
4	Dock Leveller 9 Ton	2200	3000	21	175,000	3,675,000	15,000	315,000
5	Retractable Dock Shelter	3000	4000	21	65,000	1,365,000	10,000	210,000
6	Sliding Glass Door	2000	2400	3	196,000	588,000	10,000	30,000
7	High Speed Door NIHVA MAKE	3000	3000	3	250,000	750,000	10,000	30,000
	Total			73		**10,959,500**		**835,000**
8	P&F Charges			3%		**328,785**		
	Total Without Taxes					**11,288,285**		**835,000**
	GST Extra @ 18%			18%		2,031,891		150,300
	Total With Taxes					**13,320,176**		**985,300**
9	Transportation Charges					650,000		
10	Unloading Charges @ Site					150,000		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	On Concrete /Steel
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm
12	**Surface finish**	Powder Coating
13	**Honeycomb Grill**	600mm grill at 3000mm height from Bottom.
14	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

Dock Leveler

Sr. No.	Description	Specifications
1	Capacity	9 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 600 / (-) 300 mm
7	Platform Size (W x L)	2200 mm x 3000 mm
8	Lip size (W x L)	2200 x 400 mm
9	Shut Height	480 mm
10	Maximum slope can be achieved	0.1
11	Clear Pit dimensions (W x L x D)	(W) 2250mm x (L)3050 mm x (D)485 mm
12	Hydraulic power pack	Standard
13	Driver type	Direct by electric Motor
14	Motor Ratings	1 H.P
15	Pump design flow	2.5 LPM
16	Pump pressure	120 bar Operating 200 bar Max.
17	Safety valve set pressure	120 Kg/cm^2
18	Pump Type	Gear
19	Volume of oil receiver	7 Lit
20	No Of Deck cylinder	2 No
21	Lip Cylinder	1 No
22	Pair of Dock Bumper	Included

Retractable Dock Shelter

Sr. No	Description	Specifications
1	**Size**	(W) 3600 mm x (H) 4500 mm
2	**Top Curtain**	1000 mm
3	**Side Curtain**	600 mm
4	**Curtain colour**	Black
5	**Parking Guides**	White, Yellow
6	**Wall Fixings**	Concrete, Sandwich light Concrete, Load house cavity, insulated panel
7	**Top & Side Curtaiins**	Double Layer High Quality Polyester
8	**Thickness**	3.0 mm
9	**Weight**	Approx 3400 g/m2

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Sectional Door

Sr. No	Description	Specifications
1	**Model No**	OH1042P
2	**Opening Direction & Mounting**	Vertical
3	**Door produced Based on which certification**	Doors produced according to ISO 9000 or ISO 14000 certified.
4	**Opening/Closing Speed**	0,28 m/s
5	**Door Material**	GI Steel
6	**Panel Thickness**	44 mm
7	**Door sealent**	All door sealants made of EPDM rubber, temperature resistant -30/+70
8	**Water Penetration**	EN 12425 class 3
9	**Air Permealibity**	EN12426 class 3
10	**Wind Load**	EN21424 class 3
11	**Thermal Transittance**	6 W/m2K
12	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
13	**Emergency Operation**	Single phase 230V direct drive on shaft
14	**Operating Switch**	by Disengagement rope manual
15	**Environmental Green Product DeclarationCertification**	Up/Down Keypad + stopbutton
16	**Drive Unit & Mounting Type**	as per ISO 14025 and EN 15804

Automatic Sliding Door

Sr. No	Specifications :
1	**Main power supply**
2	**Operator type- Bi part operator.**
3	**User interface- Auto Partial/Auto/one way/closed including LED status**
4	**Battery- Battery 12 V power fail open**
5	**open Operator lock- Electric lock (fail safe)**
6	**Glass : 10mm thick toughened glass**
7	**Wide acid / dip acid printing of your Logo.**

High Speed Door

- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels

Sr. No	Description	Specifications
1	Use	External Door
2	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	Opening speed	3 m/s
4	Closing speed	0.8 m/s
5	Control Panel	4 Push Button operated
6	Security Features	EN 13241-1 Standard
7	Curtain	Fabric Transparent PVC section
8	Guide Material	Aluminum
9	Hood Cover	GI
10	Motor Cover	GI
11	Operator & Control	German Make Motor , VFD
12	Connecting Voltage	220V , 1Ph , N
13	Open-Stop-Close Button	Standarad
14	Protection Category	IP 54 / IP 65
15	Power Consumption	0.75 kw Motor
16	Emergency Off Button	Standard
17	Closing Zone Monitoring	Optical Safety edge
18	External Route Monitoring	Photocell
19	Emergency Opening	Crank Handle
20	Pulll cord Cable and Vision Window	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% along with confirmed purchase order & Balance before dispatch

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333.**

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd