NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

HIRANANDANI COMMUNITIES
Mumbai
Maharashtra -India.

Date : 21.01.2020
Quote NO : SQT.19-20_2353_A
Kind Attn : Mr. SILAMBHARASAN. P
Email Id : psilambarasan@hrealty.com
Contact No: 8939828669

Project Name & Location: HIRANANDANI PARKS, Chennai

Subject : Quotation for Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
	Option 1 : Indirect Drive Motor							
1	**GI Motorized Rolling Shutter Weight - 1800 Kg**	7500	8000	2	4,86,000	9,72,000	15,000	30,000
2	**GI Motorized Rolling Shutter Weight - 1680 Kg**	7000	8000	7	4,66,000	32,62,000	15,000	1,05,000
3	**GI Motorized Rolling Shutter Weight - 780 Kg**	6500	4000	1	2,22,000	2,22,000	15,000	15,000
4	**GI Motorized Rolling Shutter Weight - 221 Kg**	2450	3000	7	90,000	6,30,000	15,000	1,05,000
				Total		50,86,000		2,55,000
5	P&F Charges			3%		**1,52,580**		
	Total Without Taxes					**52,38,580**		**2,55,000**
	GST Extra @ 18%			18%		9,42,944		45,900
	Total With Taxes					**61,81,524**		**3,00,900**
6	Transportation Charges					**Extra at Actual**		
7	Unloading Charges @ Site					**In client scope**		

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
	Option 2 : Direct Drive Motor							
1	**GI Motorized Rolling Shutter Weight - 1800 Kg**	7500	8000	2	6,61,000	13,22,000	15,000	30,000
2	**GI Motorized Rolling Shutter Weight - 1680 Kg**	7000	8000	7	6,41,000	44,87,000	15,000	1,05,000
3	**GI Motorized Rolling Shutter Weight - 780 Kg**	6500	4000	1	4,04,000	4,04,000	15,000	15,000
4	**GI Motorized Rolling Shutter Weight - 221 Kg**	2450	3000	7	1,34,000	9,38,000	15,000	1,05,000
				Total		71,51,000		2,55,000
5	P&F Charges			3%		**2,14,530**		
	Total Without Taxes					**73,65,530**		**2,55,000**
	GST Extra @ 18%			18%		13,25,795		45,900
	Total With Taxes					**86,91,325**		**3,00,900**
6	Transportation Charges					**Extra at Actual**		
7	Unloading Charges @ Site					**In client scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Rolling Shutter

Sr. No	Specification	GI Motorized Rolling Shutter - Indirect Drive	GI Motorized Rolling Shutter - Direct Drive
1	**Description:**	Motorised Rolling Shutter with GI Laths with	Motorised Rolling Shutter with GI Laths with thickness of
2	**Mounting Location area**	Inside area / Outside area	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel &	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick GI	The panel made of 1.0mm thick GI
5	**Curtain panel size**	75mm wide	75mm wide
6	**Curtain Profile**	Curved	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft	M.S. Tubular Pipe with Flange & machined shaft at the
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the	MS Plate 3 mm to 10 mm thick, as per the opening
11	**Hood Cover**	Made of GI Sheet Thickness 1.2 mm GF mm with	Made of GI Sheet Thickness 1.2 mm GF mm with
12	**Surface finish**	PU paint or Powder coated	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection	Electric Motor - Direct Mounting – IP54 Protection

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd