NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ion Exchange (India) Ltd.
ION House, Dr. E. Moses Road, Mahalaxmi, Mumbai-400 011, India.

Date : 27.03.2021
Quote NO : SQT.20.21.2994R4
Kind Attn : Bindiya Chavda
Email Id : bindiya.chavda@ionexchange.co.in
Contact No: 989212 2553

Subject : Revised Quotation for Automatic Telescopic Three Leaf Sliding Gate (Laser Cutting on Sheet)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Three Leaf Sliding Gate with Louvers (Laser Cutting on Sheet)**	4500	1800	2	513,000	1,026,000	Inclusive	
2	**Compound Wall Railing**	4870	850	6	114,000	684,000	Inclusive	
3	**Manual Swing Gate With Wicket Gate**	4300	2100	1	166,000	166,000	Inclusive	
				Total		**1,710,000**		-
3	P&F Charges			0%		-		
	Total Without Taxes					1,710,000		-
	GST Extra @ 18%			18%		307,800.00		-
	Total With Taxes					**2,017,800**		-
4	Transportation Charges					Inclusive		
5	Unloading Charges @ Site					Inclusive		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Three Leaf Sliding Gate with Louvers (Laser Cutting on Sheet)

Sr .No.	Specification	Telescopic Three Leaf Sliding Gate with Louvers (Laser Cutting on Sheet)
1	Door type	Motorised Three Leaf Telescopic Sliding Gate
2	Clear Opening gate dimension	(W) 4500 mm X (H) 1800 mm
3	Master Leaf Size	2400 X 1800 mm
4	1 ST Leaf Size	2400 X 1800 mm
5	2 ST Leaf Size	2400 X 1800 mm
6	Opening Direction	Horizontal - from left to right or reverse
7	Mounting Location area	Inside area
8	Design Pattern	Standard Tubular Design Pattern
9	Outer Frame Tube Sizes	40X40X3 MM THK SQ. TUBE
10	Internal Vertical Tube Sizes	40X40X3 MM THK SQ. TUBE
11	For Post	100X50X4.5 MM THK SQ. TUBE
12	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
13	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings
14	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
15	Painting	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
16	Control Panel	2 Nos Operating Station.(Motor Panel and Security Room)
17	Operation	By Telescopic Mechanism
18	Accessories	1. Limit Switch for Cut out when Gate is fully Closed
		2. Flashing Light
		3. Remote
		4. Hooter
		5. Photocell

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Mumbai (Ion Exchange Office - Mahalakshmi)

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 15% Advance against Bank Garranty, 70% against delivery of material on site and remaining 15% immediate after succesful installation.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd