NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Mitsubishi Electric Automotive India Pvt. Ltd.
Plot No. 167-170, Sector-5,
IMT-Manesar, Distt. Gurgaon-122050
Haryana-India.

Date : 27.08.2019
Quote NO : SQT.19.20.1979
Kind Attn : Mr. Vijender Sharma
Email Id : vijender.sharma@meai-india.com
Contact No: **9711786195**

Project Name & Location: Mitsubishi Electric Automotive India Pvt. Ltd., Haryana

Subject : Quotation for Goods Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Electro Hydraulic Goods Lift	1300	1700	1	6,97,700	6,97,700	20,000	20,000
				Total		**6,97,700**		**20,000**
2	P&F Charges			3%		**20,931**		
	Total Without Taxes					**7,18,631**		**20,000**
	GST Extra @ 18%			18%		1,29,354		3,600
	Total With Taxes					**8,47,985**		**23,600**
3	Transportation Charges					**60,000**		
4	Dismantling Charges					**35,000**		
5	Tools for Installation					**20,000**		
6	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

DETAILS	SPECIFICATION
Capacity	2000 KGS
No of Mast	II
Platform Size	1700mmL x 1300mmW
Lowered Height	300 MM
Lifting Height	7000 MM
Cylinder Hydraulic	SINGLE ACTING CYLINDER
Cylinder	2 NOS
Hydraulic Cylinder	70 Bore
Electric Motor	Siemens three phase 7.5HP
Valve Block	Hitek
Tank Capacity	40 Liter
Pump Capacity	9 LPM
Power Supply	415V
Hydraulic Hoses	Parker make
Return line filter	Hydroline make
Pressure Gauge	Wika
Suction Strainer	Hydax
Bell Housing & Coupling	Hyzen
Control Panel	Nihva
Contactor	Siemens/ L& T
Overload Relay	Siemens/ L& T
Hose burst valve	STD
Phase Indicator	ITC/Ideal/Teknik
Hydraulic Power Pack	7.5HP
Limit Switches	Teknik
Transformer	STD
Painting	As per req.
Delivery	5 to 6 Weeks
Railing Height	3 Feet

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd