NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Siemens Limited
Airoli, Navi Mumbai

Project, Location : Navi Mumbai

Date : 27.1.2021
Quote NO : SQT.20.21.2977
Kind Attn : Jayeshbhai Makwana
Email Id : jayeshbhai.makwana@siemens.com
Contact No: 8879581750

Subject : Quotation for Albany Rapid Rollup Door RR300S

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Albany Rapid Rollup Door RR300S**	2100	3000	1	559,000	559,000	20,000	20,000
	Total			**1**		**559,000**		**20,000**
2	P&F Charges			3%		16,770		
	Total Without Taxes					575,770		20,000
	GST Extra @ 18%			18%		103,638.60		3,600
	Total With Taxes					**679,409**		**23,600**
3	Transportation Charges					Extra at atcual		
4	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Albany Rapid Rollup Door RR300S

Sr. No	Description	Albany Rapid Rollup Door RR300S (100% Imported with all components – made in Germany)
1	Construction:	High-Speed Roller Door with transparent curtain and reinforcement stripes according to the following RAL colours: blue (RAL 5002) or red (RAL 3002)
2	Side frames	Side frames galvanized, bottom rail profile made of aluminium
3	Drive Unit	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
4	Control system	Controls ACS 50, IP 55 for opening / closing speed approx. 1,0 m/s. Control box with Up-Stop-Down button. For dimensions > 3500x3500mm it is obligatory to use a frequency converter control ('MCS-FC or MCC)
5	Power supply	3/(N)/PE/230/400/415 V, 50 Hz.
6	Safety features	Safety edge, safety photocell Transmitter / Receiver inside side frames, emergency crank and mechanical drop-down protection.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd