NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/18-19/0045 **Date : 13-04-2018**

INDAMAR AVIATION PVT LTD
Hanger no 1 , Juhu airport
Vile Parle (w) Mumbai 400056
Maharashtra, India

Kind Attn : Mr. Yogender Kumar
Email : yogendrak@indamer.com
Contact No :

Project Name & Location : Indamar, Nagpur

Subject : Supply of Sliding Gate, Swing Gate, Fire Rated Rolling Shutter, Rolling Shutter, Fire Rated Steel Door

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Three Leaf Motorised Telescopic Bi Parting Sliding Gate with Painting**				
1	**Size: (W) 35m X (H) 1.2m** • OUTER Frame –100X100X4mm • INNER TUBES - 25X25X2mm • Gap between tubes – 150 mm	1	No	34,50,000	34,50,000
2	Installation Charges for Above Gates	1	No	50,000	50,000
	Total				**35,00,000**
B	**Motorised Single Leaf Sliding Gate**				
1	**Size: (W) 5.5 m X (H) 1.2m** • OUTER Frame –100X100X4mm • INNER TUBES - 25X25X2mm • Gap between tubes – 150 mm	1	No	6,50,000	6,50,000
2	Installation Charges for Above Gates	1	No	20,000	20,000
	Total				**6,70,000**
C	**Manual Doubel Leaf Swing Gate**				
1	**Size: (W) 9 m X (H) 2.1m** • OUTER Frame –100X100X4mm • INNER TUBES - 25X25X2mm • Gap between tubes – 150 mm	4	No	3,23,000	12,92,000
2	Installation Charges for Above Gates	4	No	20,000	80,000
	Total				**13,72,000**
				Total value of Gates (A)	**55,42,000**

Sr	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**2 Hr. Fire Rated Rolling Shutter** **Shutter Slats:** Zinc coated steel solid slats**, Slat Thickness:** 1.0mm thick**, Shutter Guide:** Galvanize Steel, 3mm thick**, Operated by:** Motorize with one unit push button switch & manual override				
1	Size : (W) 3000 mm x (H) 3000 mm	3	No	3,45,000	10,35,000
2	Size : (W) 3000 mm x (H) 2400 mm	3	No	3,05,000	9,15,000
3	Installation Charges for Fire Rated Rolling Shutter	6	No	20,000	1,20,000
	Total				**20,70,000**
B	**Motorised Non Fire Rated Rolling Shutter** GI Slat: 1 mm Thk, Curved Type Profile with heavy duty Shaft, Guide, Hood Cover - 0.9mm, Motor - Indirect Drive with painting				
1	Size : (W) 3000 mm x (H) 3000 mm	1	No	1,28,000	1,28,000
2	Installation Charges for Rolling Shutter	1	No	20,000	20,000
	TOTAL				**1,48,000**
	Total value of Rolling Shutter (B)				**22,18,000**

Sr No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**2 Hrs (120 Min.) Fire rated Door** Fire rated Door with Rockwool Infill .GI Sheet Doors panel with 46mm thk & 1.2mm Face Sheet.Frame 1.5mm thk. and 100X57mm Jamb depth & width				
1	Single Leaf 2 Hrs Fire Rated Door **Size : (W)1200 x (H)2400 mm**	13	No.s	41,700	5,42,100
	SS Ball Bearing Hinge 102X76X3mm - Make Dorma				
	Door Closure. Make Ryobi				
	Panic bar- Single Point- IR-Briton 378 E				
	External Trim- IR- Briton 1413E				
	Vision Panel- 300 x 200 mm- Promacler 120				
	Anchor Fastener				
2	Double Leaf 2 Hrs Fire Rated Door **Size : (W)2000 x (H)2400 mm**	5	No.s	67,120	3,35,600
	SS Ball Bearing Hinge 102X76X3mm - Make Dorma				
	Door Closure. Make Ryobi				
	Panic bar- Single Point- IR-Briton 378 E				
	Panic Bar (Double Point)-IR- Briton 376 E				
	External Trim- IR- Briton 1413E				
	Flush Bolt				
	Vision Panel- 300 x 200 mm- Promacler 120				
	Anchor Fastener				
3	Double Leaf 2 Hrs Fire Rated Door **Size : (W)2400 x (H)2400 mm**	6	No.s	80,120	4,80,720
	SS Ball Bearing Hinge 102X76X3mm - Make Dorma				
	Door Closure. Make Ryobi				
	Panic bar- Single Point- IR-Briton 378 E				
	Panic Bar (Double Point)-IR- Briton 376 E				
	External Trim- IR- Briton 1413E				
	Flush Bolt				
	Vision Panel- 300 x 200 mm- Promacler 120				
	Anchor Fastener				
4	Installation charges for above fire rated door	24	No	7,000	1,68,000
		Total Value of Fire Door (C)			**15,26,420**

Grand Total of above products (A+B+C)	92,86,420
Transportation charges for above products	2,50,000
Loading & Unloading	50,000
Lifting Equipments	50,000
Final Value	**96,36,420**

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Scaffolding require for Installation it is in client scope.

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to
3 Billing will be as per the supply of material ,not as per site measurements

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	at Site
2	**P & F Charges**	:	NIL
3	**Freight Notes**	:	Mentioned above
4	**Delivery**	:	7 -8 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST @18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification /Information in this Concern.

With Best Regards

Arjun Patil
8551096333
For Nihva Technologies Pvt Ltd