NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Siemens Limited
Transformer Factory, Airoli
Mumbai

Date : 01.10.2019
Quote NO : SQT.19.20.1886R2
Kind Attn : Mr. Sunil Kushwah
Email Id : sunil.kushwah@siemens.com
Contact No: **9820180430**

Project Name & Location: Siemens Limited, Mumbai

Subject : Revised Quotation for GI Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	NIHVA Make GI Motorised Rolling Shutter	4020	5800	1	4,19,500	4,19,500	20,000	20,000
2	NIHVA Make GI Motorised Rolling Shutter	6000	6000	1	5,02,500	5,02,500	20,000	20,000
				Total		**9,22,000**		**40,000**
3	P&F Charges			3%		**27,660**		
	Total Without Taxes					**9,49,660**		**40,000**
	GST Extra @ 18%			18%		1,70,939		7,200
	Total With Taxes					**11,20,599**		**47,200**
4	Transportation Charges					**In NIHVA Scope**		
5	Unloading Charges @ Site					**In NIHVA Scope**		
6	Scaffolding					**In NIHVA Scope**		
7	Structure					**In NIHVA Scope**		
8	Tools & Tackles					**In NIHVA Scope**		
9	Dismentling of Previous Door					**In NIHVA Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

1. GI Rolling Shutter

Sr .No.	Specification	Motorized Rolling Shutter
1	Description:	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Drive Unit & Mounting Type	Direct Drive, Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection
14	3 Station Push Button	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
3	Any civil / masonry/structural work required	In Client Scope
4	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
5	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 -6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd