NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Parekh Prints
1st Floor, Italian Textile Compound, Itt Bhatti,
Goregaon-Vikroli Link Road, Goregaon East, Mumbai 400 063

Date : 15.07.2020
Quote NO : SQT.20.21.0019
Kind Attn : Mr. Triveni Soni
Email Id : triveni.soni@pispl.in
Contact No: **7898047286**

Subject : Quotation for Dock Leveller and Dock Shelter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Dock Leveller - 6 Ton	2250	2750	6	2,05,000	12,30,000	15,000	90,000
2	Retractable Dock Shelter	3500	3500	12	1,15,000	13,80,000	15,000	1,80,000
				Total		**26,10,000**		**2,70,000**
			P&F Charges	3%		**78,300**		
			Total Without Taxes			**26,88,300**		**2,70,000**
			GST Extra @ 18%	18%		4,83,894		48,600
			Total With Taxes			**31,72,194**		**3,18,600**
			Total Supply + Installation With Taxes					**34,90,794**
3	Transportation Charges					**Extra at Actual**		
4	Unloading Charges @ Site					**In client scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Dock Leveler





Sr. No.	Description	Specifications
1	Capacity	6 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 / (-) 250 mm
7	Platform Size (W x L)	2250 mm x 2750 mm
8	Lip size (W x L)	2250 x 400 mm
9	Shut Height	480 mm
10	Overall length	2250mm x 2750mm + Lip Length (400mm)
11	Maximum slope can be achieved	10%
12	Clear Pit dimensions (W x L x D)	(W) 2300mm x (L)2750 mm x (D)485 mm
13	Hydraulic power pack	Standard
14	Driver type	Direct by electric Motor
15	Motor Ratings	1 H.P
16	Pump design flow	2.5 LPM
17	Pump pressure	120 bar Operating 200 bar Max.
18	Safety valve set pressure	120 Kg/cm²
19	Pump Type	Gear
20	Volume of oil receiver	7 Lit
21	No Of Deck cylinder	2 No
22	Lip Cylinder	1 No
23	Pair of Dock Bumper	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Retractable Dock Shelter



Retractable Dock Shelter



Docking System (Sectional Door, Dock Leveler, Dock Shelter)

Sr. No	Description	Specification
1	Size	(W) 3500 mm x (H) 3500 mm
2	Top Curtain	1000 mm
3	Side Curtain	600 mm
4	Quantity	12 Nos
5	Curtain colour	Black
6	Parking Guides	White, Yellow
7	Wall Fixings	Concrete, Sandwich light Concrete, Load house cavity, insulated panel
8	Top & Side Curtaiins	Double Layer High Quality Polyester
9	Thickness	3.0 mm
10	Weight	Approx 3400 g/m2

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 to 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance and Balance before dispatch

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd