NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SWANI SPICE
Plot no-A-189/190/819, MIDC Industrial Estate,TTC,
Thane Belapur Road, Opp. Village Khairane, Navi Mumbai- 400705.

Date : 16.04.2021
Quote NO : **MHE_21.22.0004**
Kind Attn : Mr. Rajesh Patil
Email Id : maintenance@swanispice.com
Contact No: 9833984898

Project Name & Location: Inclined Screw Conveyor, Navi Mumbai

Subject : Quotation for Inclined Screw Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges for all at a time installation.	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Inclined Screw Conveyor Length 2.8 mtr**	1	1,95,000.00	**1,95,000.00**	**15,000.00**	**15,000.00**
2	**Inclined Screw Conveyor Length 3.5 mtr**	1	2,21,000.00	**2,21,000.00**	**15,000.00**	**15,000.00**
	Total			**4,16,000.00**		**30,000.00**
	P&F Charges	3%		**12,480.00**		**30,000.00**
	Total Without Taxes			**4,28,480.00**		**30,000.00**
	GST Extra @ 18%	18%		**77,126.40**		**5,400.00**
	Total With Taxes			**5,05,606.40**		**35,400.00**
3	Transportation Charges					**Extra At Actual**
4	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Inclined Screw Conveyor

Parameters	Specification
Type	Tabular Inclined Screw Conveyor
MOC	SS 304
Outer Tube Dia 6"-sch	40 mm
Inner Screw Shaft Dia 2"-sch	160 mm
Screw Flights	3 mm thk
Gear box Make	Bonfiglioli
Gear Box Type	Hollow shaft- W-86 UFC 1 10 P100 B5 B3
Motor	3 HP - 1450 rpm, 3 phase
Trolley Stand material	SS-304, 50mm x50mm x3 mm thick , revolving wheels with stopper
Tail Shaft, End Shaft, UCF	209 bearing
Top & bottom side window for cleaning purpose.	

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 4 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd