VIJAY SYSTEMS ENGINEERS PVT. LTD.

35, Chandivali Village, Off Saki Vihar Road, Anbdheri East, Mumbai - 400 072

GST REG 27AABCV973K1ZN

REF NO. E01581 /R0/PD/ 1936 /2017 24.03.2018

NHIVA TECHNOLOGIES
PUNE

K.A. MS VARSHA

Sub Offer for supply and installation of fire Curtains .
Ref. : your enquiry through email dated 20.03.2018 for Fire curtains

S.No.	ITEM DESCRIPTION	Qty (Nos.)	Size of civil opening		Head Box Size depth X height (mm)	INR Amount Supply EACH	INR Amount Supply for given qty	INR Amount Installation EACH	INR Amount Installation for given qty
			width mm	height mm					
1	COOPER FireMaster@ active fire barrier - VarioSpeed™6.0 complete with Galv. MS headboxing , side & adjustment channels and jumbo bottom bars with 24Vdc motors for power up operation with 100% TRUE gravity fall-safe fixed into 70mm-100mmØ (standard barrel size) steel rollers with EFP™ 4/1000 fabric curtains (silver/grey). Complete system tested in accordance with BS EN 1634-1:2008 FOR 120 MINUTES integrity and radiation classified as E120 EW30 C2 Grade3 in accordance with BS EN 13501-2:2007+A1:2009. Fabric in compliance with the requirements of class 0 to meet approved document B (Volume 1 &2) 2006 edition "fire safety" to the England and Wales Building regulations 2000; including split drop delay, control panel & Retract Buttons.								
1.1	FC1	3	6700	4000	180x340	627000	1881000	25000	75000
1.2	FC2	1	6000	4700	200X400	633000	633000	25000	25000
1.3	FC3	1	19500	4000	180X340	1230000	1230000	40000	40000
1.4	FC4	1	6000	4300	200X400	625000	625000	25000	25000
1.5	FC5	1	6000	4300	200X400	625000	625000	25000	25000
1.6	FC6	1	6000	4500	200X400	630000	630000	25000	25000
1.7	FC7	3	6900	7000	200X400	752000	2256000	25000	75000
1.8	FC8	1	6000	2700	180X340	560000	560000	25000	25000
	TOTAL PRICE	12					8440000		315000
	(CGST 9% + SGST9%) ON SUPPLY 18 % HSN CODE 85437099	18.00%					1519200		
	(CGST 9% + SGST9%) ON INSTALLATION @ 18% SAC CODE 998739	18.00%							56700
	TOTAL INCLUDING GST						9959200		371700
	GRAND TOTAL					10330900			

TERMS AND CONDITIONS

1 SCOPE- OUR SCOPE INCLUDES SUPPLY AND FIXING OF FIRE CURTAINS AS PER ABOVE PRICE SHEET
THE SIDE JAMBS/WALL READY TO TAKE FIRE CURTAIN SIDE CHANNEL INSTALLATION SHALL BE PROVIDED BY YOU
THE TOP BEAM OR SLAB SHALL BE PROVIDED FREE OF SERVICES TO INSTAL HEAD BOX WITH ANCHOR FASTENERS
STEEL BEAM FOR SUPPORT REQUIRED IF ANY INCLUDING ITS FIRE PROOFING NOT INCLUDED IN OUR SCOPE

2 EXCLUSION- ANY CIVIL OR FABRICATION WORK BEFORE AND AFTER FIXING OF CURTAINS NOT IN OUR SCOPE
SAFE STORAGE OF MATERIALS NOT IN OUR SCOPE. STORES SHALL BE PROVIDED BY YOU.
SCAFOLDING REQUIRED FOR INSTALLATION (PROVIDE, ASSEMBLE & REMOVE)SHALL BE IN YOUR SCOPE.
SUPPLY AND INSTALLATION OF WIRING FOR POWER SUPPLY TO CONTROL PANEL AND
SUPPLY AND INSTALLATION OF CONTROL CABLES FROM FIRE ALARM PANEL FOR ACTIVATION NOT IN OUR SCOPE.
THE FIRE BARRIER ABOVE SUPPORT BEAM UPTO TRUE CEILLING NOT IN OUR SCOPE
THE STANDARD COLOUR OF HEAD BOX AND SIDE CHANNELS SHALL BE RAL 9010 OFF WHITE.

3 GOVT. LEVIES - 18% GST ON SUPPLY AND 18% GST ON INSTALLATUON CHARGES IS CONSIDERED.
ANY VARIATION, ADDITION OR NEW IMPOSITION OF GOVT LEVIES SHALL BE CHARGED EXTRA AT ACTUALS .
ROAD PERMIT FOR DESPATCH SHALL BE PROVIDED BY CLIENT.

5 TRANSPORTATION- INCLUDED.
COOPERS UK TO MUMBAI BY SEA FREIGHT. MUMBAI TO BANGALORE BY ROAD TRANSPORT
UNLOADING OF MATERIAL SHALL NOT BE IN OUR SCOPE.

6 DELIVERY- THE MATERIAL SHALL BE DELIVERED IN 10 TO 11 WEEKS FROM RECEIPT OF TECHNICALLY
& COMMERCIALLY CLEAR ORDER & DRAWING APPROVAL AND ADVANCE.

7 VALIDITY- OUR OFFER IS VALID FOR 30 DAYS AND SUBJECT TO OUR RECONFIRMATION THEREAFTER.

8 INSTALLATION - THE INSTALLATION SHALL BE COMPLETED IN 4 TO 5 WEEKS.
SUBJECT TO CLEAR SITE FRONT AVAILABILITY OF ALL OPENINGS TO INSTALL.

9 FACILITIES TO BE PROVIDED TO US FREE OF COST AT SITE - COVERED SAFE LOCKABLE STORAGE, STAGING , ELECTRICITY,WATER

10 WARRANTY- 12 MONTHS MANUFACTURER'S WARRANTY FROM THE DATE OF SUPPLY. MAXIMUM WARRANTY ACCEPTED UPTO 30.09.2019

11 PAYMENT TERMS-
SUPPLY
50% NON RECOVERABLE ADVANCE
50% WITHIN 15 DAYS OF DELIVERY OF MATERIAL AT SITE
INSTALLATION
100% WITHIN 15 DAYS OF INSTALLATION

12 JURISDICTION-ALL TRANSACTIONS AGAINST ABOVE OFFER SHALL BE SUBJECT TO MUMBAI JURISDICTION ONLY.

13 PLEASE PLACE SEPARATE ORDERS FOR SUPPLY AND INSTALLATION ON ADDRESS MENTIONED ABOVE

FOR Vijay Systems Engineers Pvt. Ltd.

Pradeep Dani
Vice President (Sales & Marketing)
091 9552002768