Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.877 **Date:28/10/2018**

Dyna Filters

Plot no. 14 & 15 Ramtekdi Industrial Estate, Pune-Solapur Road, Hadapsar,
Pune - 411028
Maharashtra -India

Kind Attention: Mr. Rahul Raut

Phone: +91-9881476252-
Email ID: purchase3@dynafilters.com

Project Name And Location : Motorised Roller Conveyor at Pune

Subject : Quote for - Dyna Filters

Dear Sir,

Thank you for your opportunity and trust shown on “NIHVA.” your preferred partner for innovative solutions.This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer :-

Sl.No.	Description	Price	Qty	Total
1.	Roller Conveyor 1 Length ocf conveyor 2.5 meters 2 Height - top of roller 329 mm (overall 391 mm) 3 Width of conveyor (innerer) 1190 mm 4 Speed of conveyor- liner 3 Meters/min 5 Speed variation NA 6 Conveyor capacity 600 kg/meter 7 Weight of conveyed product 300 kgs approx. 8 Component details 9 Rollers Roller Dia. 76, SS 304 10 Pitch of roller 160 MM 11 Height adjustment +/- NA 12 Drive coupled with chain and drive shaft 13 Geared Motor bonfigloli, 1 HP 14 Loop to loop drive Chain 15 Sprockets En8 hardens 16 Tensioning With out scale 17 Srructure SS sq pipe and angle 18 Side guide 50 MM In built 19 Stringer SS angle with powder coat with RAL 9002 20 Jack base NA 21 90 Degree Bend NA 22 Cover for motor NA 23 Cycal cont 24 MOC SS304 25 Hardware HT allan head bolts 26 Control unit Overload and on off 27 FEATURES SS BOTTOM TRAY UNDER THE ROLLER TO COLLECT DUST PARTICLES OF SIZE 1190 X 650 MM APPROX.-02 NOS. Perforation at right side of `C' Channel, Perforated plates between two rollers	₹ 351,000.00	1	₹ 351,000.00

Grand Total **₹ 351,000.00**

GST Pune	27AAECN0437H1ZM

Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.877 **Date:28/10/2018**

Note:-

General Pre requisite at site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required
5 Scaffolding require for Installation it is in client scope

Limit of Supply

1 Provide place to store the material to be installed
2 Be responsible for the safe custody of all material
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel

Client Scope

1 Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Existing/Repair/ Modification/ Refurbishment charges will be extra

Terms & Conditions

1 **Price** : Ex works Pune
2 **P & F Charges**: @3% of Total Supply Value
3 **Freight Notes**: Extra as applicable
4 **Payment**: 80% Advance along with confirm purchase order & Balance 20% before dispatch
5 **Taxes**: GST @ 18%
6 **Validity**: Validity of Offer is 15 days from the date of quotation.
7 **Warranty**: 12 months from the date of supply
8 **Delivery** : 6-8 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
9 **Insurance :** Extra As applicable

Please feel free to Contact **Mr. Bhavin Jain - +91-8551092333** for any further Clarification /Information in this Concern.

With Best Regards

Pratiksha Prajapati
+91-7219207333
For Nihva Technologies Pvt Ltd