**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**P & G**
Plot no. 1, industrial area Katha,
baddi solan - 173205

**Project, Location : Baddi.**

**Date :** 3.08.2021
**Quote NO :** SQT.20.21.3008R3
**Kind Attn :** Ashwin
**Email Id :** Kumar.a.29@PG.com
**Contact No:** 9318792319

**Subject : Revised Quotation for ASSA ABLOY High Speed Door - RR355**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | Option I | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **ASSA ABLOY High Speed Door - RR355** | 3000 | 3400 | 1 | 957,000 | 957,000 | 15,000 | 15,000 |
| | **Total** | | | **1** | | **957,000** | | **15,000** |
| 2 | P&F Charges | | | 3% | | 28,710 | | |
| | **Total Without Taxes** | | | | | 985,710 | | 15,000 |
| | GST Extra @ 18% | | | 18% | | 177,428 | | 2,700 |
| | **Total With Taxes** | | | | | **1,163,138** | | **17,700** |
| 3 | Transportation Charges | | | | | Extra at atcual | | |
| 4 | Unloading Charges @ Site | | | | | In Client Scope | | |
| | | | | | | | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**ASSA ABLOY High Speed Door - RR355**

| Sr .No. | Specification | ASSA ABLOY High Speed Door - RR355 |
|---|---|---|
| 1 | Door curtain | transparent material with reinforcement stripes, ultramarine (similar to RAL 5002) or red (similar to RAL 3002) |
| 2 | Wind resistance | class 2 (EN 12424) |
| 3 | Bottom profile | Anodized aluminum |
| 4 | Knock out capability | After a crash it repairs automatically by activating the “close” button |
| 5 | Drive unit | Gear motor |
| 6 | Protection | IP 55 |
| 7 | Control system | Frequency converter control system Albany MCC, based on vector control including boost function at start-up. Graphic display and foil keypad for easy guided operation. Easy access to all important information for operation and service. |
| 8 | Supply voltage | 3L(N)PE/380/400/415/440/480V;50/60Hz, |
| 9 | Opening/closing speed | up to max. 2.5 / 1.0 m/s |
| 10 | Safety devices | patented, contact-free pre-running safety photocell with integrated cable chain in the side frames, stationary safety photocell, drop down protection by integrated balancing system |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAFCN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description |
|---|---|
| 1 | Secured and fully covered Store area to keep the material |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site |
| 3 | Electrical Supply on the site single phase/three phase points at different places. |
| 4 | Any civil / masonry/structural work required |
| 5 | All structure support required |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. |
| 7 | Conduits, Cables required |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

**With Best Regards**
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd