NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ratilal Bhagwandas Construction & Company Pvt. Ltd. Private Limited
Pune

Date : 23.08.2019
Quote NO : SQT.19.20.1965A
Kind Attn : Mr. Sanjay Mulay
Email Id : sanjay.mulay@ratilal.in
Contact No: **9881196056**

Project Name & Location: Jejuri, Pune

Subject : Quotation for Rolling Shutter & Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2 & 3
C.	General Conditions	4
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Single Leaf Sliding Gate (Manual)	1800	2100	1	80,000	80,000	10,000	10,000
2	Single Leaf Cantilever Gate (Manual)	6000	1800	1	5,46,000	5,46,000	20,000	20,000
3	Wicket Gate	1500	1200	1	40,000	40,000	10,000	10,000
4	GI Rolling Shutter (Motorised)	3000	3000	1	91,900	91,900	20,000	20,000
5	Gi Rolling Shutter (Gear Operated)	3000	3000	1	74,000	74,000	20,000	20,000
				Total		**8,31,900**		**80,000**
6			P&F Charges	3%		**24,957**		
			Total Without Taxes			**8,56,857**		**80,000**
			GST Extra @ 18%	18%		1,54,234		14,400
			Total With Taxes			**10,11,091**		**94,400**
7			Transportation Charges			**In Client Scope**		
8			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Slliding Gate

Sr. No	Description	Specifications
1	**Door type**	Manual Sliding Gate
2	**Clear Opening gate dimension**	(W) 6000 mm X (H) 1800 mm
3	**Opening Direction**	Horizontal - from left to right or reverse
4	**Mounting Location area**	Inside area
5	**Design Pattern**	Standard Tubular Design Pattern
6	**Outer Frame Tube Sizes**	72 x 72 x 3.2 mm
7	**Internal Vertical Tube Sizes**	38 x 38 x 2.6 mm
8	**Gap Between Tubes**	125 mm C/C
9	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	**Full Height Column sizes**	100 x 100 x 3.2 mm
12	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
13	**Painting**	Powder Coating
14	**Metal Rack**	Zinc plated metal rack
15	**Installation Checks**	need to be check = space requirements + substructure + Mounting access

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Sutter

Door type	Motorized Rolling Sutter
Door type	(W) 3000 mm x (H) 3000 mm Qty - 1
Clear Opening dimension (w) - - x (h) --	Vertical - from bottom to Top
Opening Direction	Inside area / Outside area
Mounting Location area	Side Brackets: Optional = On Concrete /Steel & Sideuides Guides: Not required for height below 3000mm
Mounting Surface	GI
Curtain material	The panel made of 1.0mm
Curtain Panel	75mm wide
Curtain panel size	Corrugation
Curtain Profile	0.9 mm to 1.2 mm (As per IS 6248)
Slat Thickness	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension
Hood Cover	Made of GI Sheet Thickness 0.8 mm with 25x25x3mm angle stiffener
Surface finish	
Painting	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer
Options Available	Perforation in Slat Profile / Rolling Grill
Automation	
Drive Unit & Mounting Type	Electric Motor (Imported China make) (single phase / three phase) - Indirect Mounting
Emergency Operation	Manual Hand Driven
Operating Switch	Push Button from inside

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd