NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

AkzoNobel India Limited
Plot No 1/1 ,TTC Industrial area ,
Thane Belapur Road ,KoparKhairane,Navi Mumbai -400710

Date : 11.03.2021
Quote NO : **AS_20.21.0018**
Kind Attn : Mr. Damodar Patro
Email Id : damodar.patro@akzonobel.com
Contact No: 8238007617

Project Name & Location: Robotic Palletizer, Navi Mumbai

Subject : Quotation for Robotic Palletizer 10Kg Payload

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**ROBOTIC PALLETIZER** Robot IRB 660-180Kg Payload Pick & Place Gripper 1 mtr Length Roller Conveyor with Sensor & Stopper Mechanism Fencing from All Sides of Robot Integration	**1**	**43,93,000**	**43,93,000**	**75,000**	**75,000**
		Total	**43,93,000**			**75,000**
2	P&F Charges	3%	**1,31,790**			
	Total Without Including Taxes		**45,24,790**			**75,000**
	GST Extra @ 18%	18%	**8,14,462**			**13,500**
	Total Amount Including Taxes		**53,39,252**			**88,500**
3	Transportation Charges		**Extra At Actual**			
4	Insurance		**Extra At Actual**			
5	Unloading Charges @ Site		**In client Scope**			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Robotic Palletizer 10Kg Payload

Parameters	Specification		
Pack Sizes	10 lit & 20 lit		
10 lit Pack size	Bottom Dia.-225 mm	Top Dia.-260 mm	Ht.-395 mm
20 lit Pack size	Bottom Dia.-270 mm	Top Dia.-305 mm	Ht.-400 mm
Pallet Dimension	1220 mm (L)	1220 mm (W)	130 mm(H)
Pallet M.O.C.	Metal / Wooden		
Matrix to be Formed for Palletizing	4 x 4 x 3 layers for 10 ltr		
	4 x 4 x 2 layers for 20 ltr		
Robot speed	5 cycles / min		
No of Packs per Grip	2 packs		
Output speed	12 packs for 20 ltr / min		
Robot Make	ABB		

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 12-14 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd