NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Larsen & Toubro
ESP office 1st Floor, Gate no.15
L&T Hazira Manufacturing Complex
Hazira, Gujarat-394510, India

Date : 16.07.2022
Quote NO : RR_22.23.0073
Kind Attn : Mr. Giriraj Parmar
Email Id : giriraj.parmar@larsentoubro.com
Contact No: 82 001 31 838

Project Name & Location: Larsen & Toubro, Surat

Subject : Commercial Offer for Retractable Freestanding Tunnel

Dear Sir / Ma'am,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size (mm)	Qty	Supply Charges in INR	
			(Nos)	Unit Price	Total Amount
1	**Retractable Freestanding Tunnel**	• 20000 W X 80000 L X 5000 H • Hot galvanized steel structure pvc fabric all around without sliding pvc curtains • Installation Inclusive	1	70,00,000	70,00,000
			Total		**70,00,000**
		Total Without Taxes			**70,00,000**
2		GST Extra @ 18%	18%		**Extra At Actual**
3		P&F Charges @ 3%	3%		**Extra At Actual**
4		Transportation Charges			**In Client Scope**
5		Lifting of equipments			**In Client Scope**
6		Unloading Charges @ Site			**In Client Scope**

B) Technical Specification

1. RETRACTABLE FREESTANDING WAREHOUSE : offers a covered area either near the borders of the propriety or in open spaces like courtyards and large squares to stock and protect packed material of all kinds enabling loading/unloading operations under any weather condition.
2. THE CARRYING STRUCTURE : consists of arcs connected to one another by pantograph bars all in galvanised steel with no need of maintenance. Sliding is performed forged and turned steel wheels provided with double ball bearings positioned in a safety casing, with a device with a special profile 8mm thick, which is windproof and prevents derailment. Sliding ground tracks are made of a pressed galvanised steel profile, 5 mm thick, and are complete with brackets or bored plates to be anchored to a layer of reinforced concrete.
3. COVERING : consists of a PVC fabric, weighing 900 g/m2, reinforced in parts mostly subject to wear and tear. It offers high resistance against atmospheric agents and guarantees very long life.
4. WORKING TEMPERATURE: -30°C +70°C
5. FIRE RETARDANT: Class 2
6. FIXING OF THE PVC FABRIC ON THE STRUCTURE : In order to avoid friction and consequently the wear out of the fabric, the joint plates of edges are rounded, this also enables a better tension of the fabric. On the longest trusses the fabric is protected from wear a tear thanks to a double layer of PVC in those points where friction is more frequent. The fabric is anchored to the steel structure by means of welded plates with double steel rings and belts with a breaking strength up to 350kgs.
7. THE FRONTAL AND REAR HEAD : are shut in the upper part with a fixed PVC cover anchored to the structure by means of a screwed-on glass-fiber reinforced plastic profile; the lower part can eventually be shut by two half curtains (opened from the center) which slide on an above track through carriages with double ball bearings. They are reinforced by means of metal vertical tubes inserted in pockets created along the curtain about every meter. At the end of the tubes there are locks which are anchored to the ground allowing or a partial opening of the curtain or block it completely. As an alternative to curtains, you can choose among the different types of industrial closing systems such as PVC fast-closing doors or folding, sliding and sectional doors

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Continuous uninterrupted access to installation section or as agreed seperately.
2. Provision of 230 V power supply for hand tools.
3. A dry and secure area, not in direct sunlight is to be provided for storage of product component
4. Access to site between 7 am to 8 pm should be provided.
5. Any storage costs for material due to delay outside of NIHVA, will be in client scope.
6. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practice. We reserve the right to extend the period accordingly.
7. Installation will start after receiving of Site Readiness Photographs or written Email communication.
8. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.
9. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
10. If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.
11. After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.

Note: Please find below List which are in Client Scope

Sr. No		Remark
1	Secured and fully covered Store area to keep the material.	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site.	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required.	In Client Scope
5	All structure support required.	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material, the additional quantities and wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 10-12 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing Approval.

Payment : 80% Advance along with Confirmed Purchase Order.
20% before Dispatch of Material.

Validity : Validity of Offer is 5 days from the date of quotation.

Warranty : 12 months from the date of supply. It only covers damage caused due to mechanical system not due to natural calamity.

Design Clause : NIHVA shall be deemed the authors of their respective concept and drawings with reserved rights, including copyrights. It shall not be used by the owner for future additions or alterations to this Project or for another project or should not copied at any other future project or should not transfer or copied by anyone.

Compensation Clause : Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA a compensation of 25% of order value.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd